

Staging Opportunities for Project X

Steve Holmes
on behalf of the PX Team

**Accelerator Physics and
Technology Seminar
May 8, 2012**





-
- Project Goals/Reference Design
 - Staging Scenarios
 - R&D Program
 - Status and Strategy

Our websites:

<http://projectx.fnal.gov>

<http://projectx-docdb.fnal.gov>

Project Goals

Mission Elements




- A neutrino beam for long baseline neutrino oscillation experiments
 - 2 MW proton source at 60-120 GeV
- MW-class low energy proton beams for kaon, muon, neutrino, and nuclei based precision experiments
 - Operations simultaneous with the neutrino program
- A path toward a muon source for possible future Neutrino Factory and/or a Muon Collider
 - Requires ~4 MW at ~5-15 GeV
- Possible missions beyond particle physics
 - Energy applications





3 MW @ 3 GeV
200 kW @ 8 GeV
2 MW @ 120 GeV



Reference Design Capabilities



- 3 GeV CW superconducting H- linac with 1 mA average beam current.
 - Flexible provision for variable beam structures to multiple users
 - CW at time scales $>1 \mu\text{sec}$, 20% DF at $<1 \mu\text{sec}$
 - Supports rare processes programs at 3 GeV
 - Provision for 1 GeV extraction for nuclear energy program
- 3-8 GeV pulsed linac capable of delivering 300 kW at 8 GeV
 - Supports the neutrino program
 - Establishes a path toward a muon based facility
- Upgrades to the Recycler and Main Injector to provide ≥ 2 MW to the neutrino production target at 60-120 GeV.

⇒ Utilization of a CW linac creates a facility that is unique in the world, with performance that cannot be matched in a synchrotron-based facility.

Reference Design Performance Goals



Linac

Particle Type
Beam Kinetic Energy
Average Beam Current
Linac pulse rate
Beam Power
Beam Power to 3 GeV program

H⁻
3.0 GeV
1 mA
CW
3000 kW
2870 kW

Pulsed Linac

Particle Type
Beam Kinetic Energy
Pulse rate
Pulse Width
Cycles to MI
Particles per cycle to MI
Beam Power
Beam Power to 8 GeV program

H⁻
8.0 GeV
10 Hz
4.3 msec
6
 2.6×10^{13}
340 kW
200 kW

Main Injector/Recycler

Beam Kinetic Energy (maximum)
Cycle time
Particles per cycle
Beam Power at 120 GeV


120 GeV
1.4 sec
 1.6×10^{14}
2200 kW

simultaneous





- Briefing to DOE/OHEP on January 27, 2012
- Staging principles
 - Significant physics opportunities at each stage
 - Cost of each stage substantially <\$1B
 - Achieve full Reference Design capabilities (including upgradability) at end of final stage
 - Fit within a funding profile devoting <20% of OHEP budget to construction projects in any year
- We presented a four stage plan, consistent with these principles.
- We subsequently provided DOE with cost profiles for the first three stages, including possible international in-kind contributions.



Staging Alternative



Staging Options

Stage 1



- Note: Proton Improvement Plan (PIP) is scoped to support Proton Source operations through 2025
- Scope
 - 1 GeV CW linac injecting into upgraded Booster
- Performance
 - 1 MW at 1 GeV
 - ~1.2 MW at 120 GeV, up to 0.8 MW at 60 GeV (if utilize all Booster cycles)
- Utilization of the existing complex
 - Booster, Main Injector and Recycler (with PIP)
 - NuMI (upgraded) or LBNE target system
 - Muon Campus
 - 400 MeV Linac retired – eliminates major reliability risk
- Physics Program
 - Long and short baseline neutrinos
 - Rare kaons from MI (slow-spill)
 - Muon campaign
 - Ultra-cold neutrons and edms
 - Materials and energy applications test facility

Stage 1 Performance Goals (Proton Source)



		NOvA/LBNE		PX Stage 1		
MI/Recycler						
	Beam Energy	120	60	120	60	GeV
	Cycle Time	1.33	0.80	1.20	0.80	sec
	Protons per pulse	4.9E+13	4.9E+13	7.5E+13	7.5E+13	ppp
	Slip Stacking Efficiency	95	95	95	95	%
	Beam Power	0.70	0.58	1.20	0.90	MW
	Normalized Beam Emittance (95%)	20	20	20	20	π mm-mr
	Laslett Tune Shift (injection)	-0.06	-0.06	-0.09	-0.09	
Booster						
	Injection Energy (Kinetic)	0.4	0.4	1.0	1.0	GeV
	Injection Momentum	1.0	1.0	1.7	1.7	GeV/c
	Extraction Energy (Kinetic)	8.0	8.0	8.0	8.0	GeV
	Revolution Period (Injection)	2.2	2.2	1.8	1.8	μ sec
	Cycles to Recycler	12	12	12	12	
	Booster Cycle Rate	15	15	15	15	Hz
	Beam Cycle Rate	9	15	10	15	Hz
	Protons per Pulse	4.3E+12	4.3E+12	6.6E+12	6.6E+12	
	Injection Time	0.02	0.02	1.05	1.05	ms
	Injected Turns	9	9	613	613	
	Average Delivered Beam Power	49	82	84	126	kW
	Normalized Beam Emittance (95%)	20	20	20	20	π mm-mr
	Laslett Tune Shift (injection)	-0.35	-0.35	-0.21	-0.21	
Linac						
	Beam Energy (Kinetic)	0.40	0.40	1.00	1.00	GeV
	Beam Momentum	0.95	0.95	1.70	1.70	GeV/c
	Beam Current	35.0	35.0	1.0	1.0	mA
	Linac Beam Duty Factor	1.8E-04	2.9E-04	1.1E-02	1.6E-02	
	Beam Power to Booster	2	4	11	16	kW
	Full Momentum Deviation over Injection Time	0.0	0.0	8.3	8.3	MeV/c

Stage 1

Performance Considerations




- Linac
 - Beam current
 - Duty factor?
- Booster
 - H- injection @ 1 GeV, 500-600 turns
 - Beam acceleration/transition
 - Longitudinal emittance
 - Note: Booster has operated above $6E12$ in studies (longitudinal emittance?)
- Recycler
 - Slip stacking: require $\Delta p(95\%) = \pm 8$ MeV/c from Booster
- Main Injector
 - Acceleration/transition
- NuMI target
 - >1 MW operations?

⇒ Task Force established to develop a conceptual plan

Stage 1

Alternative (“PLL”) Location





- Scope
 - 1-3 GeV CW linac
 - 3 GeV experimental facilities + 2 experiments
- Performance
 - 3 MW at 3 GeV
 - ~1.2 MW at 120 GeV, 0.8 MW at 60 GeV (if utilize all Booster cycles)
- Utilization of the existing complex
 - Booster, Main Injector and Recycler (with PIP)
 - NuMI (upgraded) or LBNE target system
- Physics Program
 - Long and short baseline neutrinos
 - MW-class kaon and muon physics programs
 - Ultra-cold neutrons and edms
 - Materials and energy applications test facility

Staging Options

Stage 3



- **Scope**
 - 3-8 GeV pulsed linac
 - Main Injector Recycler upgrades
 - Short baseline neutrino facility/experiment
- **Performance**
 - 3 MW at 3 GeV
 - 50-200 kW at 8 GeV
 - >2 MW at 60-120 GeV
- **Utilization of the existing complex**
 - Main Injector and Recycler
 - LBNE beamline/target
 - 8 GeV Booster retired – eliminates major reliability risk
- **Physics Program**
 - Multi-MW long and short baseline neutrinos
 - MW-class kaon and muon physics programs
 - Ultra cold neutrons and edms
 - Materials and energy applications test facility

Staging Options

Stage 4



- **Scope – beyond the Reference Design**
 - Current upgrade of CW and pulsed linac
 - Main Injector & Recycler upgrades
 - Step toward a NF or MC
- **Performance**
 - 3 MW at 3 GeV
 - 4 MW at 8 GeV
 - >2 MW at 60-120 GeV
- **Utilization of the existing complex**
 - Main Injector and Recycler
 - LBNE beamline/target
- **Physics Program**
 - Long baseline with ultra-high power low & high energy neutrino sources
 - Ultra-high power short baseline neutrinos
 - MW-class kaon and muon physics programs
 - Materials and energy applications test facility



Program:	NOvA + Proton Improvement Plan	Stage-1: 1 GeV CW Linac driving Booster & Muon, EDM programs (MI>80 GeV)	Stage-2: Upgrade to 3 GeV CW Linac (MI>80 GeV)	Stage-3: Project X RDR (MI>60GeV)	Stage-4: Beyond RDR: 8 GeV power upgrade to 4MW
MI neutrinos	470-700 kW**	515-1200 kW**	1200 kW	2300 kW	2300-4000 kW
8 GeV Neutrinos	15 kW + 0-50 kW**	0-40 kW* + 0-90 kW**	0-40 kW*	85 kW	3000 kW
8 GeV Muon program e.g, (g-2), Mu2e-1	20 kW	0-20 kW*	0-20 kW*	85 kW	1000 kW
1-3 GeV Muon program	-----	80 kW	1000 kW	1000 kW	1000 kW
Kaon Program	0-30 kW** (<30% df from MI)	0-75 kW** (<45% df from MI)	1100 kW	1100 kW	1100 kW
Nuclear edm ISOL program	none	0-900 kW	0-900 kW	0-900 kW	0-900 kW
Ultra-cold neutron program	none	0-900 kW	0-900 kW	0-900 kW	0-900 kW
Nuclear technology applications	none	0-900 kW	0-900 kW	0-900 kW	0-900 kW
# Programs:	4	8	8	8	8
Total* power:	585-735 kW	1660-2240 kW	4230 kW	5490 kW	11300kW

* Operating point in range depends on MI energy for neutrinos.

** Operating point in range is depends on MI injector slow-spill duty factor (df) for kaon program.



- Goal is to mitigate risk: technical, cost, and schedule
- Primary elements of the R&D program:
 - Primary technical risk element is the front end
 - CW ion source/RFQ
 - Wideband chopping with high (1×10^{-4}) extinction rate
 - (Low- β) acceleration through superconducting resonators with minimal halo formation
 - MEBT beam absorber (>8 kW)
 - Development of an H- injection system
 - Superconducting rf development
 - Cavities, cryomodules, rf sources – CW to long-pulse
 - High Power targetry
 - Upgrade paths: Multi-MW low energy neutrinos and Muon Collider
 - *All of these elements are required at Stage 1, with the exception of 1.3 GHz pulsed RF*
 - First and third elements addressed in an integrated system test: PXIE
- Goal is to complete R&D phase by the end of 2016

Operating Scenario 3 GeV Program



1 μ sec period at 3 GeV

Muon pulses (12e7) 162.5 MHz, 80 nsec

700 kW

Kaon pulses (12e7) 27 MHz



1540 kW

Nuclear pulses (12e7) 13.5 MHz

770 kW


Ion source and RFQ operate at 4.4 mA

77% of bunches are chopped @ 2.1 MeV \Rightarrow maintain 1 mA over 1 μ sec





- PXIE is the centerpiece of the Project X R&D program
 - Integrated systems test for Project X front end components
 - Validate the concept for the Project X front end, thereby minimizing the primary technical risk element within the Reference Design.
 - Operate at full Project X design parameters
- Systems test goals
 - 1 mA average current with 80% chopping of beam delivered from RFQ
 - Efficient acceleration with minimal emittance dilution through ~30 MeV
 - Achieve in 2016
- PXIE should utilize components constructed to PX specifications wherever possible
 - Opportunity to re-utilize selected pieces of PXIE in PX/Stage 1
- Collaboration between Fermilab, ANL, LBNL, SLAC, India




PXIE will address the address/measure the following:

- Ion source lifetime
- LEBT pre-chopping
- Vacuum management in the LEBT/RFQ region
- Validation of chopper performance
- Kicker extinction
- Effectiveness of MEBT beam absorber
- MEBT vacuum management
- Operation of HWR in close proximity to 10 kW absorber
- Operation of SSR with beam
- Emittance preservation and beam halo formation through the front end




- Whitepaper available describing rationale, goals, plan
 - Shared with DOE


<http://projectx-docdb.fnal.gov/cgi-bin/ShowDocument?docid=966>
- Technical Review March 6-7
- <https://indico.fnal.gov/conferenceDisplay.py?confId=5278>
- Preferred location identified (CMTF)
- Cost estimate /funding plan will allow completion of the full scope of PXIE in 2016
 - Requires maintenance of Project X and SRF budgets at FY12 levels
- DOE has requested that we organize and execute PXIE as a “project”, not a “Project”
 - Organization Chart
 - Program Design Handbook
 - Resource Loaded Schedule
 - DOE oversight
 - Periodic reporting
 - Periodic review




SRF R&D Technology Map



Section	Freq	Energy (MeV)	Cav/mag/CM	Type
HWR ($\beta_G=0.1$)	162.5	2.1-10	8/8/1	HWR, solenoid
SSR1 ($\beta_G=0.22$)	325	10-42	16/10/ 2	SSR, solenoid
SSR2 ($\beta_G=0.47$)	325	42-160	36/20/4	SSR, solenoid
LB 650 ($\beta_G=0.61$)	650	160-460	42 /14/7	5-cell elliptical, doublet
HB 650 ($\beta_G=0.9$)	650	460-3000	152/19/19	5-cell elliptical, doublet
ILC 1.3 ($\beta_G=1.0$)	1300	3000-8000	224 /28 /28	9-cell elliptical, quad



Example: SNS, 805 MHz, $\beta=0.81$



CW Linac assumptions:


162.5 MHz	$B_{pk} < 60\text{mT}$
325 MHz	$B_{pk} < 70\text{mT}$
650 MHz	$B_{pk} < 70\text{mT}$
1300 MHz	$B_{pk} < 80\text{mT}$

$$\Rightarrow E_{acc} = 15.6 \text{ MV/m}; Q_0 \sim 1.7 \cdot 10^{10} @ 2 \text{ K}$$


SRF Acceleration Parameters



Energy Gain



Beam Power




SRF Development Cavity/ CM Status



- 1300 MHz
 - 90 nine-cell cavities ordered
 - 60 received (32 from U.S. industry: 16 from AES, 16 from Niowave-Roark)
 - ~ 40 processed and tested, ~20 dressed
 - 2 CM built: one from a DESY kit and a second U.S. procured
 - CM1 testing at NML is complete; CM2 was delivered to NML April 26 for testing
- 650 MHz
 - JLab built two single-cell $\beta = 0.61$ cavities
 - Six $\beta = 0.9$ single-cell cavities ordered from U.S. industry recently arrived
 - Order for six $\beta = 0.61$ (2 JLab, 2 FNAL design) single-cell cavities in industry
- 325 MHz
 - 2 SSR1 $\beta = 0.22$ cavities (Roark, Zanon) both VTS tested
 - 1 of these dressed and tested at STF
 - 2 SSR1 being fabricated in India (IUAC, spring 2012)
 - 10 SSR1 ordered from Industry (Niowave-Roark)
 - 6 delivered; 1 VTS tested, second soon to follow
- Design work advanced on 325 MHz CM, but proceeding with lower priority on 650 MHz CM (not required in PXIE)


Project X 162.5 and 325 MHz Cavities






- HWR ($\beta_G = 0.11$) Half Wave Resonator
 - EM and mechanical design underway at ANL
 - Similar to cavities & CM already manufactured by ANL




- SSR1 ($\beta_G = 0.22$) Single Spoke Resonator
 - Initiated under HINS program → more advanced
 - 8 prototype cavities to date
 - 3 tested as bare cavities at 2K
 - One dressed and tested at 4.8K




- SSR2 ($\beta_G = 0.47$) Single Spoke Resonator
 - EM design complete
 - Mechanical design in progress





- Three bare cavities tested; the second one met the PX specification
 - Need to understand difference between March 2009 and April 2012 cavities
- One dressed cavity tested at 4.8K
 - Modifications in process to allow dressed cavity testing at 2 K

650 MHz Cavity E-M Design (Fermilab)



β_G	0.61	0.9	
Length (from iris to iris)	705	1038	mm
Aperture	83	100	mm
Cavity diameter	389.9	400.6	mm
R/Q, Ohm	378	638	Ω
G - factor	191	255	Ω
Max. gain per cavity ($\phi=0$)	11.7	19.3	MeV
Gradient	16.6	18.6	MV/m
Max surface electric field	37.5	37.3	MV/m
E_{pk}/E_{acc}	2.26	2.0	
Max surf magnetic field	70	70	mT
B_{pk}/E_{acc}	4.21	3.75	mT/(MeV/m)



- For purposes of cryogenic system design, the dynamic heat load limited to 250 W at 2K per cryomodule
 - <35W per cavity ($\beta_G = 0.61$) and <25W per cavity ($\beta_G = 0.9$)
 - $Q_0 = 1.7E10$
- Multiple single cells received from JLab and industry




$\beta=0.9$, AES




$\beta=0.6$ /JLab

- Five-cell design complete for $\beta_G = 0.9$ cavities
 - Four 5-cell $\beta_G = 0.9$ cavities on order from AES; two expected in FY12



650 MHz

Single Cell Performance (JLab, $\beta=0.6$)



Project X Centrifugal Barrel Polishing IB4 Tumbling Machine




C. Cooper Recipe Media


- Multi-step process for elliptical cavities using multiple sets of media
- Potential for up to 4 cavity-cycles per week

Project X Centrifugal Barrel Polishing

9-Cell Results



ACC015
Before CBP



After CBP and 40 μ m EP

- Demonstrated cavity gradients > 35 MV/M
- Drastic reductions in acid use.
- Demonstrated as a cavity repair method.

SRF Plan

Cavities & Cryomodules



Integrated SRF Plan																					
Cryomodule Construction																					
U.S. Fiscal Year	FY08		FY09		FY10		FY11		FY12		FY13		FY14		FY15		FY16		FY17		
1.3 GHz																					
CM1 (Type III+)		Omnibus Delay	CM fab			Install CM1	CM1 Test		CC1 Rework	CM1 Rework					ASTA Operational w/beam				TBD		
CM2 (Type III+)			Order Cav & CM Parts	Process & VTS/Dress/HTS			CM fab	swap	CM2 Test	CM2 Test w/beam	Install 3 CM										
CM3 (Type IV: 2/5/8)			Design	Order Cav & CM Parts					CM fab												
CM4 (Type IV: 2/5/8)					Order Cavities & CM Parts (ARRA Funded)				CM fab						Test in CMTS						
CM5 (Type IV: 2/5/8)											CM fab						Test in CMTS				
CM6 (Type IV: 2/5/8)														CM fab					Test in CMTS		
650 MHz																					
Single Cell Design & Prototype						Prototypes	Process & VTS														
LE 650 five cell Design & Prototype											Prototypes (2)	Process & Test	HTS-2 testing								
LE 650 five cell (India)												Prototypes (2+1) India		Process & Test	HTS-2 testing						
HE 650 five cell Design & Prototype							Prototypes (2+ 2)	Process & Test				Dress cavities	HTS-2 testing								
HE 650 five cell (India)												Build 650 Cav in India		Process & Test	HTS-2 testing						
HE_650_CM1												Concept Design	Design with India	Procure Parts in India		650 CM Ass'y					
325 MHz																					
SSR1 Design & Prototype						Procurement (14 in progress)	Process & VTS/Dress/STF					SSR1 Cav Ready									
SSR2 Design & Prototype																Design	Prototypes	Process & VTS			
CM325_SSR1_proto CM										Design & Prototype	Order 325 CM Parts	325 CM Ass'y		Test @ PXIE							
162.5 MHZ HWR CM (ANL)										Design & Prototype	Order Cav & CM Parts		Process & Test		HWR CM Ass'y		Test @ PXIE				



SRF Plan Infrastructure



Infrastructure Construction											
U.S. Fiscal Year	FY08	FY09	FY10	FY11	FY12	FY13	FY14	FY15	FY16	FY17	
ANL/FNAL Cavity Handling Upgrades	Omnibus Delay					Upgrade Complete					
VTS-1 650 MHz Upgrade					Upgrade Complete						
CAF CM Assembly Upgrade		1300 Upgrade Complete					325 Upgrade Complete		650 Upgrade Complete		
650 MHz Dressing CAF Upgrade								Upgrade Complete			
VTS 2 & 3 Upgrade			Procure			VTS 2/3 Complete					
HTS 2 cryostat (India)				Design		Procure India		HTS2 Complete			
Cave, RF & Cryo Distribution					Design	Procure					
NML Injector & BL		Design	Procure		Install & commission	NML Beam available			NML Beam available		
NML Cryo Distribution System						Procure		NML Dist Complete			
CMTF CM Test Stand (CMTS1) India					Design	Procure India		CMTS1 Complete			
CMTS-2 (650 CW CM test stand) India						Design	Procure India		CMTS2 Complete		
2K Superfluid Refrigerator			Design	Procure		Install & comm			NML 500 W Superfluid Refrigerator Operational		
SLAC Refrigerator				Refurbish		Install & commission			SLAC Refrigerator Operational		
CMTF Cryo Distribution System								CMTF Dist Complete			
MDB Spoke Test Facility 2k Upgrade						Ready					
AES 1300-650 EP / 325 BCP facility		Design	Procurement		EP/BCP ready						
ANL EP/BCP 650 Upgrade		ANL 1300 EP ready Oper	Design 650 EP	Procure	650 EP Ready						






- Need to accumulate 26 mA-ms protons in the MI/Recycler (RD)
 - For a stationary foil, a single 26-ms pulse would destroy the foil.
 - 6 pulses at 10 Hz provide sufficient radiative cooling between pulses
 - ~400 turns
 - Also looking at moving/rotating foils and laser assisted stripping
- 1 mA-msec protons required to load the Booster in Stage 1
 - 600 turns



Dependence of maximum foil temperature on time, only radiative cooling is taken into account



- 162.5 and 325 MHz sources will be solid state
 - ~5-20 kW/unit
- Evaluating multiple technologies for 650 MHz
 - IOT
 - Solid State
- 1300 MHz (Stage 3) would be based on klystrons



EFFICIENCY - WHY?

- Operating cost
- Cooling requirements
- Reliability

Project X Status and Strategy



- Project X strategy is strongly tied to the overall DOE Intensity Frontier Strategy
 - LBNE: What will or will not be done is in a state of flux at the moment
 - Two Task Forces established at Fermilab
- Project X strategy is strongly tied to the overall fiscal condition of the U.S.
 - Strong message from the DOE on staging
- We remain well supported financially for the R&D phase
 - \$13M in FY12 and FY13 + significant investment in srf
- Significant effort is going into defining the physics research opportunities at all stages
 - Recent workshops on opportunities with spallation sources and on short baseline neutrinos
 - Project X Physics Study schedule June 14-23, 2012
 - Snowmass 2013 in planning stages (DPF)
- A significant contribution from India is a strong possibility

Project X Status and Strategy



- Strategy
 - Develop the physics case and mobilize support within the community
 - Includes outreach to non-HEP communities
 - Maintain the RDR as the description of the ultimate goal
 - Maintain the cost estimate for the RDR, with the Stage 1 piece easily segregated
 - Develop a Reference Design description for Stage 1
 - Pursue the PXIE program as a priority within the Project X R&D program
 - Maintain an R&D plan based on a flat-budget
 - Be immediately responsive to DOE when they ask for information

2012 Project X Physics Study

June 14 - 23, 2012 • Fermilab • Batavia, Illinois

The Project X Physics Study will engage theorists, experimenters, and accelerator scientists in establishing and documenting a comprehensive vision of the physics opportunities at Project X, and integrating these opportunities within a coherent plan for development of detector capabilities and the accelerator complex.

Working Groups

- Long-Baseline Neutrinos
- Short-Baseline Neutrinos
- Muon Experiments
- Kaon Experiments
- Electric Dipole Moments
- Neutron-Antineutron Oscillations
- Lattice QCD
- High Rate Precision Photon Calorimetry
- Very Low-Mass High-Rate Charged Particle Tracking
- Time-of-Flight System Performance Below 10 psec
- High-Precision Measurement of Neutrino Interactions
- Large-Area Cost Effective Detector Technologies

Organizing Committee

Steve Holmes, Andreas Knuedel, Stephen Parker, Eds Ransberg, Cynthia Rossini, Bob Teuchies, Susanne Weber

For Further Information

Cynthia Rossini (crosini@fnal.gov)
Fermilab Conference Office
B13, Box 500, Batavia, IL 60510-5001

indico.fnal.gov/event/projectxps12

Fermilab | ENERGY | Office of Science



- Two MOUs covering the RD&D Phase

National

ANL

BNL

Cornell

Fermilab

LBNL

MSU

ORNL/SNS

PNNL

TJNAF

SLAC

ILC/ART

IIFC

BARC/Mumbai

IUAC/Delhi

RRCAT/Indore

VECC/Kolkata

- Informal collaboration/contacts with CERN/SPL, ESS
China/ADS, UK, Korea/KoRIA
- Weekly Friday meeting:
<https://indico.fnal.gov/categoryDisplay.py?categId=168>
 - Collaborator participation via webex
 - Meeting notes posted
- Semi-annual Collaboration meetings



- The Reference Design represents a unique facility, which would form the basis for a decades long, world leading Intensity Frontier program at Fermilab
 - Project X Reference Design concept has remained stable for two years
- Funding constraints within the DOE have led us to identify staging scenarios
 - Stage 1, based on a 1 GeV CW linac feeding the existing Booster, represents a very significant step in performance of the Fermilab complex, and offers both compelling physics opportunities and a platform for further development toward the Reference Design.
- R&D program underway with very significant investment in srf
 - Emphasis on the CW linac/Stage 1 components, including front end development program (PXIE)
- Significant effort is being invested in defining physics programs associated with all stages

⇒ Go to Bob Tschirhart's colloquium tomorrow to hear more about this!

“Project X and the Endless Frontier”, Fermilab Colloquium, Wednesday, May 9



650 MHz Five-Cell Cavity and CW CM Design Status


Project X




- Cavity drawing package and specification done

- CW CM conceptual design advanced
 - stand-alone 8-cavity cryomodule
 - Overall length: ~12 m, 48 " O.D.



5-cell $\beta = 0.9$



- Stiffening rings located to minimize dF/dP while maintaining tunability



Concept utilizing blade tuner




Collab with India

650 MHz Cavity ($\beta_G=0.6$)






- Standard processing including light BCP (no EP)
- Spec: $Q_0 > 8.8E9$ at 2K for $E_{acc}=16$ MV/m and $Q_0 > 1.3E10$ at 2K for $E_{acc}=19$ MV/m
 - Q_0 requirement achieved at 16 MV/m for cavity #2
- Further surface processing likely to bring both cavities up to performance requirement;
- EP may not be required
- Mechanical studies required to extend design to 5-cell





- New Muon Lab (NML) facility under construction for ILC RF unit test
 - Three CM's driven from a single rf source
 - 9 mA x 1 msec beam pulse
 - Large extension and supporting infrastructure under construction
 - Refrigerator to support full duty factor operations
 - Cryomodule test stands for all frequencies
 - Building extension for additional CM's and beam diagnostic area
- The Meson Detector Building (MDB) Test Facility ultimately comprises:
 - 2.5 – 10 MeV beam (p, H-): 1% duty factor, 3 msec pulse
 - 325 MHz superconducting spoke cavity beam tests
 - Chopper tests
 - H⁻ beam instrumentation development
 - Shielded enclosures and RF power systems for testing individual, dressed 3.9, GHz, 1.3 GHz, 650 MHz, and 325 MHz superconducting RF cavities




- SSR1 ($\beta=0.22$) cavity under development
 - Two prototypes assembled and tested
 - Both meet Project X specification at 2 K
- Preliminary designs for SSR0 and SSR2


Cavity processing at Argonne

Project X
Project X



- Joint facility built by ANL/FNAL collaboration
- EP processing of 9-cells has started
- Together with Jlab, ANL/FNAL facility represents the best cavity processing facilities in the US for ILC or Project X



Ultrasonic Cleaning



Electropolishing




**High-pressure
rinse**


Fermilab SRF infrastructure



VTS



VTS



Cavity tuning machine



HTS



String Assembly



MP9 Clean Room



Final Assembly



1st U.S. built ILC/PX Cryomodule



1st Dressed Cavity



PXIE

Beam Envelopes w/ Chopping



Beam Envelopes



V. Lebedev, Jan. 9, 2012



3s beam envelopes through MEBT (top) and from RFQ end to the beam dump (bottom); rms norm. emittance 0.25 mm mrad; thick green lines show the beam envelope for beam extracted to the MEBT beam dump





TraceWin - CEA/DSM/Ifu/SACM







Gradient and energy





Phase advance Front End (w/o MEBT)

High energy
sections




Project X Emittance


Halo parameter



[1/9/2012] TraceWin - CEA/DSM/Irfu/SACM




[1/9/2012] TraceWin - CEA/DSM/Irfu/SACM



~~Initial distribution are taken from latest design of RFQ (Oct.2011, J.Staples)~~

Beam Power



Cryogenic losses/cavity

