



Managed by Fermi Research Alliance, LLC for the U.S. Department of Energy Office of Science

Plan for Establishing 700 KW Operations

Ioanis Kourbanis

MI Department


DOE 700KW Follow-up Review

11 September 2015

Introduction

- We have formulated a plan with precise timeline and milestones, to establish 700 KW operations.
- The plan includes all the hardware and operational prerequisites needed to achieve the milestones from both the MI and the Proton Source Departments.
- We are having regular and frequent communications with the Proton Source Department to ensure that the requirements from the Proton source are well understood and are on time.
- This plan is a living document updated each time a milestone is achieved or delayed with reporting at the Proton PMG.

Schedule for milestones to reach 700 KW



Booster beam parameters required for Recycler SS

<u>Parameter</u>	<u>Value</u>
Transverse Emittance	15 pi mm-mr
Long. Emittance	0.12 eV-sec
Δp	± 7.5 MeV

- **Currently the beam from Booster meets the requirements**

Roadmap to 700 KW* (FY2015)

- Switch to 2+6 Operation-March. 2015 (same power 350 KW)
 - Main Injector Department
 - Optimize slip stacking in RR
 - Commission MI collimators
 - Proton Source Department
 - Reliable 6 Hz operation with $3.2E12$ ppb and proper dp/p
- Provide 460 KW with 2+6 operation-March 2015
 - Main Injector Department
 - Minimize losses
 - Proton Source Department
 - Reliable 6 Hz operation with $4.3E12$ ppb and proper dp/p
 - At least 17 RF stations operational

DONE

DONE

*NuMI only operation

FY2015 cont.


- Demonstrate 4+6 operation by achieving 460 KW operation for at least one hour.-May 2015
 - Main Injector Department
 - Establish 4+6 operation with $3.4E12$ ppb and good efficiency.
 - Work on reducing Recycler losses.
 - Proton Source Department
 - 7.5 Hz operation with $3.4E12$ ppb and proper dp/p
 - 17 RF stations capable of 15 Hz operation

Achieved on July 1st 2015 (521KW for 1hr!)
Delayed because of Booster RF cavity failures

Current high power operation (2+6)


- On March 5th we switched to 2+6 operation, delivering ~420 KW of beam power.
 - 483 KW new MI Beam Power record (running without SY120)
 - This has been our standard operating mode till the summer shutdown.
- **We have achieved our official goal of delivering 400KW for at least one week of at least 100 hours during this year.**

2+6 operation Beam Power





Power reduction
because of NuMI horn
problems.

Machine efficiencies (2+6)





96.7%
Overall
Efficiency

RR and MI losses (2+6)





Collimation efficiency

Protons per Hour and Peak power to NuMI




FY15 NuMI Performance




4+6 Operation

- On July 1st 2015 we switched to 4+6 operation for about two hours.
- We were able to achieve 521 KW beam power for 1 hour.
 - The injected beam intensity was $3.9\text{E}12\text{p/batch}$.
 - Large beam losses but with only minimal beam tuning.

4+6 BEAM POWER




Machine efficiencies (4+6)






**93.4%
Overall
Efficiency**

Recycler losses (4+6)



Recycler beam pipe at 307,419,425 and 429 is being replaced during the shutdown.

Replaced RR beam pipes




- Recycler beam pipe in the above locations was found not to be straight with extra bad welds.
- We are replacing the beam pipe at 429 this week.

Picture of the removed RR pipe at 425



6+6 operation

- On July 2nd 2015 we established for the first time 6+6 slip stacking operation and sent beam to the NuMI target for about 2 hours.
 - Low power operation ~280KW
 - Mostly done to help Booster run 15 Hz with beam.



6+6 Recycler Beam

FY2016(1)

- Switch to 4+6 operation with 460 KW-October 2016*
 - Main Injector Department
 - Commission 4+6 operation with $3.4E12$ ppb and 95% efficiency.
 - Proton Source Department
 - Reliable 7.5 Hz operation with $3.4E12$ ppb and proper dp/p.
 - 18 Re-furbished RF stations installed (Reliability and Efficiency)
 - East and West Anode supplies completed (Reliability; Required for adding more stations)

*Assumes shutdown ends on October 4th

FY16(2)

- Achieve 575 KW with 4+6 operation-November 2016
 - Main Injector Department
 - Commission 4+6 operation with 4.3×10^{12} ppb and 95% efficiency
 - Proton Source Department
 - Reliable 7.5 Hz operation with 4.3×10^{12} ppb
 - 19 Re-furbished Booster RF stations installed(increased reliability and efficiency)
 - Booster longitudinal dampers operational(required for damping of coupled bunch instabilities)

FY16(3)

- Switch to 6+6 operation (same power 575 KW)-Jan . 2016
 - Main Injector Department
 - Commission 6+6 operation with $3.6E12$ ppb and 95% efficiency
 - Proton Source Department
 - Reliable 9 Hz operation
 - 20 re-furbished RF stations installed (Reliability and increased efficiency)
 - Provide $3.6E12$ ppb with the proper longitudinal emittance and dp/p .


FY16 (4)

- Achieve 700 KW with 6+6 operation-Feb. 2016*
 - Main Injector Department
 - Commission 6+6 operation with $4.3E12$ ppb and 95% efficiency
 - Proton Source Department
 - Reliable 9 Hz operation
 - Provide $4.3E12$ ppb with the proper longitudinal emittance and dp/p

*Recycler collimators may be required before we can run reliably at 700KW

We are working on a Recycler collimator design. Plan to install a primary collimator and at least a couple of secondary collimators next shutdown.

Beam Power vs Time





Conclusions



- We have developed a detailed plan to achieve 700-KW beam power to the NuMI target.
 - Includes requirements for both the MI/RR and the Proton Source.
 - Active document; updated each time we achieve or fail to achieve a milestone.
- We have already achieved the first 3 milestones and have delivered a record beam power of 521 KW to the NuMI target.
- We see no show stoppers achieving 700-KW to the NuMI target in FY16.
 - Continuing to address RR aperture problems and improving losses.
 - We are developing a Recycler collimation plan in order to be able to run reliably at 700KW.

EXTRA SLIDES


Booster emittances




4+6 Losses



Recycler losses vs injection number (2+6)




Recycler losses vs Injection time (4+6)





Weekly NuMI performance



RR Beam

RR and MI
efficiencies

Beam Power

RR Collimator Schematic

