

# **Run II Status**


**Mike Church**

**FNAL**

**5/05/03 Run II Director's Review**



# Integrated Luminosity History







# Peak Luminosity and Intensity History

(Through 4/30/03)

### Peak luminosity over last 12 months



### Peak Intensity over last 12 months




● protons/bunch (E9)

● pbars/bunch (E9)




# Weekly Performance

Store Hours Per Week Since 6/17/02



Weekly Downtime Since 6/17/02



(Through week of 4/21/03)




# Status on Luminosity Parameters

	<b>best luminosity store 1 year ago</b>	<b>highest luminosity store to date</b>	<b>FY03 stretch goals ("routinely")</b>
<b>max. antiproton stackrate (E10/hr)</b>	<b>10.2</b>	<b>13.1</b>	<b>18</b>
<b>antiproton stacksize (E10)</b>	<b>113</b>	<b>143</b>	<b>200</b>
<b>pbar xfer eff.</b>	<b>.39</b>	<b>.66</b>	<b>.80</b>
<b>pbars/bunch at low beta (E9)</b>	<b>11.4</b>	<b>24.6</b>	<b>31.0</b>
<b>protons/bunch at low beta (E9)</b>	<b>181</b>	<b>196</b>	<b>240</b>
<b>peak luminosity (E31 cm<sup>-2</sup>sec<sup>-1</sup>)</b>	<b>1.83</b>	<b>4.23</b>	<b>6.6</b>



# Integrated Luminosity Performance and "Stretch" Goal for FY03

## FY03 Luminosity Goals






# Beam Intensity

- **Booster can produce adequate # protons for Tevatron FY03 intensity goals**
- **Accumulator can produce (almost) adequate # antiprotons for FY03 goals**
- Emittance growth produces poor efficiencies

Efficiency for store 2328 (3/20/03)





# Proton Longitudinal Emittance

- Booster can produce  $<.15$  eV-sec bunches at required intensity (6 dipole mode dampers are effective in controlling coupled bunch instabilities).
- However, to control longitudinal instability in the MI the Booster emittance is intentionally blown up to  $\sim.3$  eV-sec/bunch (7 bunches)
- After coalescing in the MI this is  $\sim 4.0$  eV-sec.  
**This contributes to poor coalescing, poor MI  $\rightarrow$  Tev transfer efficiency, poor beam lifetime @ 150 GeV in the Tevatron, and poor acceleration efficiency**
- At low beta longitudinal emittance is  $\sim 4+$  eV-sec. Goal is 3 eV-sec.
- Longitudinal dampers will be installed in the MI in July.
- Beam loading compensation for 53 MHz RF cavities is being commissioned on the MI ramp
- "Selective" longitudinal fuzzer being developed for Booster



# Antiproton Longitudinal Emittance

- Accumulator core is kept at 25 eV-sec during shots, independent of stack size. This allows for extracting >90% of the core with ....
- extracted emittance of .8 eV-sec – 2.5 eV-sec /bunch with an average of  $\sim 1.1$  eV-sec @ 8 GeV
- MI measures  $\sim 1.5$  eV-sec before coalescing (@150 GeV),  $\sim 3.0$  eV-sec after coalescing
- Tevatron measures  $\sim 3.5$  eV-sec @ 150 GeV.
- Tevatron measures  $\sim 3.5 - 4$  eV-sec at low beta. **Goal is 3 eV-sec.**
- **No single cure: Small emittance blowups during unstacking, transfers, acceleration and coalescing:**
  - 1) **Feedforward beamloading compensation on the ramp on the 53 MHz cavities in the MI should help.**
  - 2) **Higher voltage on Accumulator unstacking cavity should improve efficiency (fewer bunches to coalesce)**
  - 3) **Long range beam-beam effects in the Tevatron may be contributing to emittance blowup??**



# Proton Transverse Emittance

- At Booster intensity of  $4.2E12$ /batch,  $\epsilon_H = 17 \pi$ -mm-mrad,  $\epsilon_V = 14 \pi$ -mm-mrad @ 8 GeV
- Coalesced beam @ 150 GeV in MI is  $\epsilon_H = \sim 19 \pi$ -mm-mrad,  $\epsilon_V = 17 \pi$ -mm-mrad
- Tevatron measures  $\epsilon_{\text{average}} = \sim 20-25 \pi$ -mm-mrad @ 150 GeV
- Tevatron emittance at low beta is  $\sim 20-25 \pi$ -mm-mrad. **Goal is 20  $\pi$ -mm-mrad.**

-Again, no single cure:

- 1) Increased efficiencies may allow for lower initial transverse emittance (higher efficiency  $\rightarrow$  fewer turns  $\rightarrow$  lower emittance).
- 2) Injection dampers in MI and Tevatron will help. (1-2  $\pi$ -mm-mrad per transfer)
- 3) Improved lattice match between MI and Tevatron will help.
- 4) Better vacuum in Tevatron will help. (long term project)



# Antiproton Transverse Emittance

- Core transverse emittance grows linearly with stack size (this is the nature of stochastic cooling).  $\epsilon_{\text{average}} = 6 \pi\text{-mm-mrad}$  @ 150 mA
- At 8 GeV in MI,  $\epsilon_{\text{average}} = 8 \pi\text{-mm-mrad}$ , becoming  $\epsilon_{\text{average}} = 10 \pi\text{-mm-mrad}$  after coalescing
- Tevatron measures  $\epsilon_{\text{average}} \sim 20\text{-}25 \pi\text{-mm-mrad}$  @ 150 GeV and @ 980 GeV

**Goal is 15  $\pi\text{-mm-mrad}$ .**

- **Major problem is the emittance blowup during the MI→Tev transfer. Not understood, but under investigation.**
- **Improved helix in the Tevatron may also reduce pbar transverse emittance blowup(??)**



# Agenda for FY03

- **3 week shutdown in January (complete)**
  - C0 Lambertson removal; Recycler vacuum upgrades and instrumentation installation; Tevatron vacuum; CDF shielding; ....
- **February to late-July**
  - deliver luminosity; up to 5 shifts/week dedicated studies; minimize shutdown days; Tevatron requires ~1 shift/week of "maintenance"  
(suffered 2 Tevatron magnet failures since shutdown)
- **6 week shutdown starting late July**
  - Recycler vacuum; e-cooling civil construction; Tevatron F0 Lambertson modification; Tevatron collimator @A4; additional shielding for CDF detector; NUMI installation work; infrastructure maintenance (full scope of work not yet determined)....
- **Continued running in Fall**
  - same as February - July



# Critical Projects for Luminosity in FY03 (1)

- **A150/P150 beamlines**

- The original scope of the work -- reduction of injection oscillations and matching of beamlines to linear lattice has been  $\sim$ completed.
- This was thought to be the major source of the problem (emittance blowup), but this does not seem to be the case.
- Beam studies and calculations underway are aimed at understanding coupling and beam-beam effects in Tevatron as a source of emittance blowup.

- **Tevatron transverse dampers**

- Transverse damper installation is complete: dampers are used at 150 GeV with positive effect -- Tevatron can run with lower chromaticity @ 150 GeV with better lifetime.
- Transverse dampers are not yet used on the ramp and squeeze because excessive coupling causes the dampers to anti-damp out-of-plane motion (not understood).
- Injection dampers to be commissioned by July. Should reduce emittance growth by  $\sim 2 \pi$ -mm-mrad for pbars and protons.
- More studies required to understand interaction of dampers with coupling



# Critical Projects (2)

- **C0 Lambertson replacement**

- Completed in January shutdown. New helix commissioning has started, but requires many study shifts (aperture scans, tune, coupling, chromaticity, feeddown corrections)
- The removal of the C0 Lambertsons has reduced transverse impedance, and has allowed the proton intensity to be increased since the January shutdown

- **Accumulator stochastic cooling bands 2&3 equalizers**

- Installed during the January shutdown.

- **AP3 beamline**

- Found a plastic magnet cap in the beamline in January shutdown (been there for ~20 years).
- Beamline well-matched to MI lattice; injection oscillations contribute  $\sim 1 \pi$ -mm-mrad to emittance growth
- Future efforts will be directed toward 8 GeV transfer reliability and faster shot setups.



# Critical Projects (3)

- **MI longitudinal dampers**

- Cavity fabrication and FPGA programming is in progress.
- High power amplifiers have been purchased. Beam studies in progress.
- Expect installation of new cavities in July

- **F0 Lambertson lamination shielding**

- Major source of transverse impedance in the Tevatron is now the F0 Lambertson magnets. Plan to shield the laminations during Summer shutdown. Should allow increase in proton intensity in Tevatron @ 150 GeV.

- **Reliability**

- VFC replacement is 95% complete; cryo wet engine rebuild is complete; compressor starter switch rebuild and cold compressor bearing replacement in progress
- Designing resonant abort kicker charging system to eliminate abort kicker prefires.
- New Tevatron magnet stands under fabrication
- Planning improved monitoring of Tevatron alignment



# Critical Projects (4)


## • Stacking upgrades

- Major emphasis has been on Debuncher momentum cooling, stacktail cooling system, and yield into Debuncher (AP2 and target).

- No real stacking improvements since mid-November when peak stacking rate of 13.1 mA/hr was achieved.

## Debuncher momentum cooling

12 Nov 02 data






# Tevatron coupling

Data shows in-plane and out-of-plane difference orbits after single horizontal kick. Data is for 1<sup>st</sup> 5 turns in Tevatron.


(from M. Syphers)



**Coupling in Tevatron is  $\sim$ uniform around the ring and is consistent with  $\sim 1.5$  units of  $a_1$  per dipole. This is compensated by a distributed skew quad circuit of 42 elements.**



# Tevatron coupling (continued)



Tevatron coil and cryostat assembly is held within the iron by 4 supports at 9 locations along the length of the magnet. Recent measurements of the “smart bolts” (upper supports) on 18 magnets in the tunnel, indicate that the coil assembly has sagged by  $\sim 2$  mils from original. This is enough to produce  $\sim 1$  unit of  $a_1$  per dipole.

In 1984, compensating skew quad circuit was running at  $\sim 2A$ . From 1995 compensating skew quad circuit has been running at  $\sim 24A$  (@ 800 GeV).

**Tevatron dipole cross section (from P. Bauer)**



# Booster Dogleg

Septum



Dogleg Magnets



- Each of the two Booster extraction septa has a set of *vertical* dogleg magnets to steer the beam around it during acceleration.
- More powerful doglegs were installed in 1998 to reduce losses early in the cycle.
- These magnets have an edge focusing effect which distorts the *horizontal* injection lattice:
  - 50% increase in maximum  $\beta$
  - 100% increase in maximum dispersion.
  - Harmonic contributions.
- Effect goes like  $I^2$ . Now tune to minimize.
- Recently got an unusual opportunity to explore potential improvements from fixing the problem.
- Working on schemes to reduce or remove problem.

**(from E. Prebys)**





# Booster Dogleg (continued)

## Ideal Lattice




## Add Doglegs






# Booster Dogleg (continued)





# Booster Performance



**Recent stacking performance.  
Also providing  $>4E16$   
protons/hour to miniBooNE**



# Recycler Commissioning

- Prior to January shutdown beam lifetime was  $>100$  hours, with equilibrium emittance of  $\sim 7 \pi$ -mm-mrad and  $\sim 75$  eV-sec with  $70E10$  antiprotons.
- During the shutdown the number of ion pumps was doubled in  $\sim 3/4$  of the ring,  $\sim 20\%$  of the ring was baked, and additional instrumentation was added.
- Since the shutdown the beam lifetime has been  $\sim 3$  times worse, and the emittance growth rate  $\sim 3$  times faster. Contaminated vacuum is thought to be the culprit.
- Some instrumentation and beampipe will be removed and those sections will be rebaked in order to recover (at least) the previous vacuum.
- Stochastic cooling systems have been commissioned; transverse emittance monitor has been commissioned; beam line tuner has been commissioned
- New BPM system is being built and is scheduled for completion of installation by July.
- Ramped correctors have been commissioned – horizontal orbit distortions due to MI 120 GeV ramp have been reduced to  $<.3$ mm rms.



# Summary

- Factor of 2.4 increase in peak luminosity over last 12 months
- Factor of 3 increase in weekly integrated luminosity over last 12 months
- Increased stacking rate and Accumulator stack size
- Progress on instrumentation
- Improvements in theoretical understanding of issues
- Plan of action for continuing improvements in luminosity