

# The NuMI Beam: A First Year of Operation Sam Childress, Fermilab



### Successes & Challenges




#### **Presentation Outline**

- NuMI / MINOS Overview
- Beam System Components
- Beam Commissioning & Transition to Operations
- > NuMI Beam Performance: Successes and Challenges
- > Summary

A previous AB seminar at an earlier stage of NuMI beam operation was given 29 Sept. 2005

### NuMI: Neutrinos at the Main Injector





Fermilab to Soudan, Minnesota

## NuMI: v's at the Main Injector (Focus of this talk) MINOS: Main Injector Neutrino Oscillation Search

#### A neutrino beam from Fermilab to northern Minnesota

- ➤ 120 GeV **protons** from the Main Injector (400 kWatts)
- > Production of a high power **neutrino** beam
- > On-axis over 735 km to Soudan mine (MINOS experiment)

#### A large near hall at ~ 1 km from the target

➤ MINOS near detector (980 Tons)


#### A deep underground hall at Soudan, Minnesota

➤ MINOS far detector (5400 Tons)

#### **Key NuMl Project Dates**

- Initiated in late 1998
- Facility construction completed in Fall 2003
- Technical component installation from 2003 to early 2005
  - Extraction & primary beam components in Main Injector interlock area installed during scheduled machine shutdown times in 2003 & 2004.
- > Beam commissioning starts Dec. 2004
- Completion of project goals Jan. 2005
  - DOE Approval for Operation

# Elevation View of the NuMI/MINOS Project on Fermilab Site



# Key NuMI Beam System Features



#### Main Injector & NuMI

Main Injector is a rapid cycling accelerator at 120 GeV

> from 8 to 120 GeV/c in ~ 1.5 s

up to 6 proton batches (~ 5×10<sup>12</sup> p/batch) are successively injected from Booster into Main Injector

Main Injector in parallel provides protons for the Collider program (anti-proton stacking )and transfers to the Tevatron) and NuMI

total beam intensity  $\sim 3 \times 10^{13}$  ppp, cycle length 2 s

#### Mixed mode: NuMI & Pbar stacking


- > two single turn extractions within ~ 1 ms:
  - 1 batch to the anti-proton target, 5 batches to NuMI
- Normally the batch extracted to the Pbar target comes from the merging of two Booster batches ("slip-stacking") (up to 0.8×10<sup>13</sup> ppp)
- > the default mode of operation is mixed-mode with slip-stacking

#### **NuMI** only


> up to 6 Booster batches extracted to NuMI in ~ 10 μs

### Extraction from Main Injector






Kickers & Septa







#### v Production for NuMI



### Reasonable Variable Energy v Beam by Moving Target distance from Horn 1





"Semi-beams"

Just moving LE target - remotely

**Full Beams** *Move Horn 2* 

### **Graphite Target**




Graphite Fin Core

2 interaction lengths

Water cooling tube provides mechanical support


Low Energy Target fits in horn without touching




#### Horn System – 2 horns

(shown in work cell, hanging from support module)






## Work Cell Mount/Dismount Components




#### Hadron Absorber



Water cooled Aluminum core, followed by Steel

Steel & concrete shielding

#### **Near Hall and Detectors**



# Beam Commissioning & Transition to Operations

#### **Pre-Beam Commissioning**

- We planned to and did establish readiness of systems for primary beam prior to first extracted beam pulses.
- > These include:
  - Magnet function & connection polarities
  - Power supply function / ramp parameters
  - Kicker & power supply function
  - Recycler shielding from EPB fringe fields
  - Instrumentation function and readout polarities
  - Beam Permit System [ establish & test 1<sup>st</sup> limits for all devices]
  - Control timing
  - Verify documentation capability Beam profiles, positions, intensity, beam loss, etc.
  - Main Injector beam suitable for extraction

#### **NuMI Initial Beam Commissioning**

- **December 3-4 2004. Commissioning the primary proton beam** 
  - > target out, horns OFF
  - $\triangleright$  small number of low intensity (1 batch with  $3\times10^{11}$  protons) pulses carefully planned
  - **beam extracted out of Main Injector on the 1st pulse**
  - beam centered on the Hadron Absorber, 725 m away from the target, in 10 pulses
  - > all instrumentation worked on the first pulse
- **❖** January 21-23 2005. Commissioning of the neutrino beam
  - $\triangleright$  target at z=-1 m from nominal  $\Rightarrow$  pseudo-medium energy beam, horns ON
  - $\triangleright$  MI operating on a dedicated NuMI cycle, at 1 cycle/minute, with a single batch of 2.6×10<sup>12</sup> protons, few pulses up to 4×10<sup>12</sup> protons
  - > final tuning of the proton line
  - > neutrino interactions observed in Near Detector
  - ➤ NuMI project met DoE CD4 goal (project completion)
- **❖** February 18-22 2005. High intensity beam in the NuMI line
  - > MI operating on a dedicated NuMI cycle in multi-batch mode
  - with 6 batches, we achieved a maximum intensity of 2.5×10<sup>13</sup> p/cycle 11 May. 2006
    S. Childress AB Seminar

#### Beam Extraction in 10 Pulses achieved to hadron absorber at 1 km distance

0.27173

0.076763

0.27173

10

10

4.7484

15

0.076763


4.6779

15

4 7484

4.6779

December 3-4, 2004



Profile monitor output along the beamline (few pulses later) (from the extraction up to the target - ~ 400 m distance)

11 May. 2006

S. Childress - AB Semina

20.000

10.000

-15

-5


Vertical Position (inches)

-10

### Most Significant Commissioning Challenge

- Interleaving beam commissioning schedule with delayed completion of target hall forced air chiller system.
- Priority to understand NuMI proton beam function while Main Injector and Collider still in start-up mode after lengthy shutdown.
  - Accomplish by discrete steps starting with very low intensity, and adding new capabilities as installation readiness completed.
    - 1st commissioning weekend was only 1.2E13 protons total with target out
    - 3<sup>rd</sup> commissioning period (10 weeks later) to 2.5E13 per pulse
  - Many thanks to Malika Meddahi for working with us during NuMl commissioning, and with our schedule uncertainties.

## **Beam Commissioning & Start up for Data Taking**



#### **Transition to Operations**

- Transition to Operations
  - VERY smooth
    - Restarted after target checkout in late April
    - Main Control Room
       Operators take control of running NuMI beam
       (12 May)
    - Initiate NuMI running during Recycler shot setup (18 May)
    - Initiate NuMI running during TeV shot setup (22 June)
      - We needed to be a "low overhead" beam to Operators to have these running modes

- Keys to NuMI Proton beam operation –
  - Comprehensive beam permit system : ~ 250 parameters monitored
  - Open extraction/primary beam apertures – capability of accepting range of extracted beam conditions
    - Superb beam loss control
  - Good beam transport stability
  - Autotune beam position control
    - No manual control of NuMl beam during operation

### NuMI Beam Performance

#### NuMl 120 GeV Primary Beam


- > Key specifications are:
  - Very low beam loss <1E-5 fractional loss for large regions of transport. (unshielded intense beam passing thru ground water reservoir)
  - Maintain position on target to 0.25 mm rms & angle to < 60 µrad.</li>
  - Intense 400 kWatt beam => tight control over residual activation
- Overall performance:
  - A strong success.

### Kicker System Requirements

#### tightened specs during design process

	Early Requirement	Final Requirement
Integrated Field	2.2 kG • m	3.6 kG • m
(120 GeV protons)	(550 µrad)	(900 µrad)
Number of Magnets	2	3
Field Flatness	± 1%	< ± 1 % (Best Effort)
Repeatability	± 1%	< ± 1/2% (Best
(over 8 hours)		Effort)
Field Rise Time	1.52 µs	
Flat top length	9.68 µs for 6 Batches, 8.08 µs for 5 Batches	
Magnetic Aperture	1.98 m x 10.7 cm x 5.2 cm (each magnet)	

### **Primary Beam Optics**




**Specifications:** fractional beam losses below 10<sup>-5</sup>

(Groundwater protection, residual activation)

11 May. 2006

S. Childress - AB Seminar



#### **NuMI Beam Permit System**


#### coordinated by R. Ducar

- > Dedicated hardware based on Tevatron fast abort system
- Permit to fire NuMI extraction kicker is given prior to each beam pulse, based on good status from a comprehensive set of monitoring inputs
  - ~ 250 inputs to NuMI BPS
- Inputs include Main Injector beam quality prior to extraction, NuMI power supply status, target station and absorber status, beam loss and position for previous pulse
- > NuMI BPS was prototyped with MiniBooNE, with excellent results
- > Very similar in function to LHC,CNGS beam interlock system

With the very intense NuMI beam, perhaps our most important operational tool.

#### **Autotune Primary Beam Position Control**

- Automatic adjustment of correctors using BPM positions to maintain primary transport & targeting positions
- Commissioned at initial turn on for correctors
- Vernier control for targeting.
   Initiate tuning when positions 75 125 microns from nominal at target
- VERY robust for a given extraction mode. Refining for alternating (interleaved) extraction modes




Autotune Beam Control Monitor

### Beam Performance plots (most plots provided by M. Bishai, BNL)


- Kicker Stability
- Shown in plots for full month of Jan.'06
  - 2.0E19 POT this month
  - 0.98 E6 pulses
- Beam position stability
  - NuMI only, mixed and interleaved modes
- > Pretarget beam widths
- Beam loss vs extraction mode
- Intensity, Beam Power & Downtimes for the 1st NuMI Year

# Measurement of Kicker Stability with Beam



- Measured Change in Position
- BPM Accuracy of ~10 μm
- Total Displacement of 43 mm


# Jan. '06 Beam Stability on Target NuMI Only




Note greatly expanded scale. Horizontal sees kicker stability effects.

Error on mean batch position < 60 microns for all batches (160 µ for batch 1)

### Jan. '06 Beam Stability on Target Mixed Mode







Hor

Ver

Note bimodal effect of Pbar kicker on 1<sup>st</sup> NuMI batch [Either even or odd # turns between extractions]. Error on mean batch position increased to 90 μ. (Many batch 1 points > 250 μ spec.)

### Beam Stability on Target Interleaved Mode







Jan 06 Nov.05

Some worsening of momentum difference between extraction modes. Are preparing separate Autotune corrector files for each.


### Jan '06 Pretarget Beam Widths



### Jan '06 Average per Pulse Primary Beam Loss – NuMl Only



## Jan '06 Average per Pulse Primary Beam Loss – Mixed Mode




Significant improvements in earlier loss from Pbar slip stacked batch

#### **Progression to Increased Beam Power**


- > Keys to improving beam power for NuMI have included:
  - Continuing enhancement in accelerator intensity capability and control of beam loss – especially for pbar slip stacking process
    - NuMi only operation has been very smooth from the beginning, but this is not the normal operational mode
  - Steady improvement in number of beam cycles available for NuMI
    - Running during Recycler and Tevatron shot transfers
    - Adapting operational modes to interleave extra NuMI cycles as pbar stacking cycle times increase (due to stacktail core cooling limitations as stack increases)
  - Targeting highest possible intensity in NuMI only mode
    - Since 20 Sep.'05 when spare NuMI target was ready

#### Normalized Neutrino Rates vs Time



#### **Near Detector**

#### CC Energy Spectra: Batch 1 vs Other Batches




11 May. 2006

#### NuMI Beam Year

#### Protons, Beam Power, Downtimes

NuMI Beam Performance, January 2005-March 2006



# Target Hall Systems

## NuMI Target Hall Systems


- > Some VERY challenging one of a kind designs
- Graphite Target
  - Target integrity for intense fast spill beam
  - Low energy beam design precludes rigid support structure
- > Horn & Reflector
  - Design for > 10 million pulses at 200 kAmps
  - Low mass to minimize secondary beam absorption
  - Intense radiation environment, moisture => corrosive effects
- Essential need for spares, with long lead times
  - Very difficult to repair relatively minor problems due to radiation
- > 240 kW forced air target chase cooling system
  - Design constraints not as fundamental, but many challenges

## System Problems and Repairs

- > Three significant component failures:
  - Target cooling line leak Mar.'05
  - Horn 2 (reflector) hard ground fault Oct. '05
  - Horn 2 cooling water flow return problem Jan.-Feb.'06
- System designs have looked toward hot component replacement, not repair.
- Success here in addressing all three problems, and continue to use these components!!
  - Significant motivation from spare readiness
  - A VERY sustained effort by J. Hylen plus engineering teams

# Target Scan using Hadron Monitor provides verification of major change – Mar. '05

Scan after water leak





Normal target scan

#### **Target Diagnosis Period**

- No NuMI beam for ~ 1 month while work to diagnose target cooling water leak
- > Target removed from beam chase to hot cell
  - Water leak has closed after moving target
  - Many diagnostic steps no firm answer for cause of water leak
  - Modifications made to fill target vacuum vessel with He gas (small overpressure)
  - Water removed by combination of He pressure and vacuum pumping
- Replace target in beam chase in preparation for operation using He backpressure to hold water out.
- Leak reopens after 1<sup>st</sup> hours of beam again, but He backpressure technique has worked very well – for the duration of the run.

## Horn 2 Ground Fault - Oct. '05

#### loose support foot on horn



Horn 2 before beam 4 cm clearance foot to floor 11 May. 2006

Owl shift Sat. Oct. 1, hard ground fault of 1 ohm.

-when Horn 2 moved to work cell ground fault cleared

-foot left behind in chase, nut had vibrated off

-scorch marks seen under foot

Moved old foot, installed new foot Wed Oct. 12, horn reinstalled,



## Horn 2 (Reflector) Repair Apr. '06

**Symptom:** Suction of water back from Horn 2 could not keep up with water spray rate to the horn – water built up in the horn


Swage-lock fitting disconnect here

Problem: hole in suction line at ceramic electrical insulator drawing in air, reducing water suction

**Repair:** replace this section

Cut 5 cm stainless pipe here

Water collection tank



# Challenge for Repair was the Residual Radiation Field

- > 0.3 0.5 Sv/hr I chase around horn before component removal
- > 0.08 Sv/hr on contact after horn removal
- Repair accomplished 18 Apr.
  - Checks good with no air or water leak
  - Hi-Pot acceptable
  - Preparing for horn pulsing vibration test
- > The ALARA radiation plan estimated about 2.8 mSv to the repair crew including 25% for contingencies. (~ 10 μ Sv per second )
- The job was done with a total dose of 2.4 mSv. With an 8 person repair crew plus radiation safety supervision.
  - Extensive prior rehearsal for all steps.

#### Repaired Horn Returning to Target Chase



Repaired line

#### Summary

- > A very eventful first year for NuMI beam operation.
- > Strong successes in commissioning for all systems.
- Excellent Main injector and NuMI proton beam performance.
  - Significant ongoing efforts toward providing more POT
- A challenging and ultimately very successful first year with target hall systems
  - Our most important success was accomplishing system repairs
  - After 7.8 Million pulses, we continue with all original components
- > Beam startup again after 3 month shutdown in June '06

## Upcoming MINOS EP Seminar at CERN

- > 5 Sept. 2006 M. Kordosky
  - Report for the full MINOS data set currently collected
  - In conjunction with the NBI2006 Workshop

March 2006 result \_\_\_\_ with 0.93E 20 POT

