




JPARC visit - T2K target hall

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 1

Tour of 50 GeV accelerator, hadron hall, T2K target hall/absorber/near detector

Had only short time with target hall experts, who are extremely busy getting ready to turn beam on to T2K target next month, but graciously took time out to show us the facility.

The timing of the trip was set by trying to get there before things became irradiated; knowing what things work well will come with a few years operating experience.



Note T2K permanent facilities (dump, shielding) designed for up to 4 MW, but replaceable items (collimator, window, target, horns) designed for 0.75 MW.

Will show

- Overview slides of beam-line "borrowed" from publicly available T2K talks
Takashi Kobayashi, Chris Densham, Atsuko Ichikawa
- A few pictures we took
- Some comparisons to NuMI
- Some comments about what is transferable to DUSEL beam

(Accuracy warning: there is a reason hear-say is not admissible in court)



Some issues for LBNE (DUSEL beam)

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 2

? surface pit versus mining for target hall

Containment of gas radio-isotopes

Very large hook-height

Shield blocks versus overhead dirt/rock

Cheaper to have very large support rooms on surface ?

? inert gas in sealed target pile

Advantages:

Reduces corrosion (e.g. NuMI nickel flakes)

Reduces and contains short-lived radio-isotopes in gas

Some reduction in tritium (significant or not?)

Dis-advantages:

No way to fix helium leak if there is a failure (?)

Significantly raises the bar for interventions in target pile

Need walls to withstand vacuum (?)

Helium is not as good at standing off high voltage for horns



Some issues for LBNE (DUSEL beam)

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylan/FNAL
Page 3

- ? failure of crane during hot pick
 - Pull component directly into coffin ?
 - Side load so don't use crane, but rollers ?
 - Put lots of redundancy on crane ?
- ? how to handle tritium
- ? inert gas around dump
- ? Monitoring beam



JPARC visit - T2K target hall

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 4

JPARC

short facility, 110 m target to dump

DUSEL

200 to 300 m DK



This and next bunch is borrowed slides

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 5

A T2K Roadmap – as of end of last year

	Day1 (up to Jul.2010)	Next Step	KEK Roadmap	Ultimate? [Not official any more]
Power(MW)	0.1	0.45	1.66	[3-4 MW] ? [Original objective]
Energy(GeV)	30	30	30	[50]
Rep Cycle(sec)	3.5	3-2	1.92	
No. of Bunch	6	8	8	[8]
Particle/Bunch	1.2×10^{13}	$< 4.1 \times 10^{13}$	8.3×10^{13}	
Particle/Ring	7.2×10^{13}	$< 3.3 \times 10^{14}$	6.7×10^{14}	
LINAC(MeV)	181	181	400	
RCS	h=2	h=2 or 1	h=1	

After 2010, plan depends on financial situation



Target station

- Target & horns
in helium vessel
- Helium vessel and iron
shields cooled by water


Decay Volume


- 94m long helium vessel cooled by water
- 6m thick concrete shield


Hadron Absorber

(Beam Dump)

- graphite core
in helium vessel








- Baffle
- 3 horns Hanged by support module.
- Target ... installed in the 1st horn.
- OTR (Optical Transition Radiation monitor): attached to 1st horn





Target Station

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 9



Beam window
(designed in RAL)










Horn & support module


NE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 11



Horn Support Module



Cast Iron Shield Block
[1/10 model]





Baffle



Helium Vessel Construction

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 12




Installation for the
bottom plates has been completed



Upper box on the Super-Carrier
(Nakaminato port)

- Installation is going on !





- Vacuum test of He vessel finished on Feb. 18th.
 - All TS+DV+BD connected to one BIG vessel ($\sim 3\text{m} \times \sim 5\text{m} \times \sim 100\text{m} = \sim 1500\text{m}^3$)
 - Evacuated down to 50 Pa by three pumps
 - No leak found after two repairs at the connection between DV-BD
- Ceiling concrete blocks will be installed from Mar. 9th to 16th.



Decay Volume

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 14





LRNE (DUSEL beam) Mfg.

Beam Window

Top plate


Ti-6Al-4V Double
Beam window

Helium inlet

Pillow seal (mates
with mirror finished
flange on either side)


Support casing

Pantograph mechanism






Helium cooling of beam window



The finished window skins
(by RAL workshop):



Helium velocity ≈ 5 m/s





Monitor stack and Window

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 17



Monitor stack (TRIUMF)
installed on Oct. 22nd.




The beam window from RAL
was installed on Oct. 23rd.





Collimator

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 18





- Beam collimator in front of the 1st horn
- Designed & Build in UK
- Installation succeeded on Jan. 10th.








OTR (Canada)

LBNE (DUSEL beam) Mtg.
March 23, 2009
FNAL
page 20

Calibration image



Backlit Foil w Holes



Undistorted



- Profile monitor just in front of target
- Foil structure is installed to 1st horn module.
- Optical path (Mirrors) is aligned and calibration image is obtained.
- Cabling, Installation of optical table on going




Target - (UK)


- Graphite rod, 900 mm (2 interaction lengths) long, 26 mm ($c.2\sigma$) diameter
- **c.20 kW (3%)** of **750 kW** Beam Power dissipated in target as heat
- Helium cooled (i)to avoid shock waves from liquid coolants e.g. water and (ii)to allow higher operating temperature
- Target rod completely encased in titanium to prevent oxidation of the graphite
- Helium cools both upstream and downstream titanium window first before cooling the target due to Ti-6Al-4V material temperature limits
- Pressure drop in the system should be kept to a minimum due to high flow rate required (max. 0.8 bar available for target at required flow rate of 32 g/s (30% safety margin))
- Target to be uniformly cooled (but kept above 400°C to reduce radiation damage)
- It should be possible to remotely change the target in the first horn



Target Design: Helium cooling path



Flow turns 180° at downstream window






Diffusion Bond +


Graphite-Graphite bonding test

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 23

IG43 Graphite diffusion
bonded into Ti-6Al-4V
titanium, Special Techniques
Group at UKAEA Culham



Graphite transfer to
Aluminium



Graphite-Graphite
bonding



Aluminium intermediate layer, bonding
temperature 550°C
Soft aluminium layer reduces residual thermal
stresses in the graphite





30 GeV, 0.4735Hz, 750 kW beam

Radiation damaged graphite assumed (thermal conductivity
20 [W/m.K] at 1000K- approx 4 times lower than new
graphite)

CFX


Maximum temperature = **736°C**



Temperature (Contour 3)

[C]



0 0.118 0.236 0.354 (m)







Helium cooling velocity streamlines

Velocity (Streamline 1) Maximum velocity = 398 m/s





Pressures (gauge)

Pressure drop = 0.792 bar







Helium-Cooled Graphite Target in the 1st Horn



CFX


Helium gas cooling system is
 in hand and being tested.


Velocity
 (Streamline 1)
 4.132e+02
 3.099e+02
 2.066e+02
 1.033e+02
 2.080e-02
 [m s⁻¹]



$\Delta T \sim 200K \sim 7MPa$ (Tensile 27MPa)

Full prototype to be
 delivered in Dec.







Pulsed beam induced thermal stress waves in target graphite

Max. Von Mises Stress = 7 MPa
- cf graphite strength ~37 MPa
- should be OK

VonMises_centre
Long_stress_centre
Hoop_stress_centre
VonMises_radius
Hoop_stress_radius

($\times 10^{**4}$)

1000

800

600

400

200

0

-200

-400

-600

-800

-1000

0

.5

1

1.5

2

2.5

3

3.5

4

4.5

5

TIME

($\times 10^{**5}$)


8 bunches/spill
Spill width
~5 μ s

VALU

Rep. rate: 0.47 Hz


Bunch spacing:
~600(300) ns

Bunch length: 58ns (Full width)





Radiation Damage in IG43 Graphite - data from Nick Simos, BNL



200 MeV proton fluence

$\sim 10^{21}$ p/cm²

c. 1 year operation in T2K

(phase 1, 750 kW)

We don't expect targets to last long!



Targets can be changed within magnetic horn



Irradiation effects on Graphite

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 30

- Expected radiation damage of the target
 - The approximation formula used by NuMI target group : 0.25dpa/year
 - MARS simulation : 0.15~0.20 dpa/year
- Dimension change : shrinkage by ~5mm in length in 5 years at maximum.
~75 μ m in radius
- Degradation of thermal conductivity ... decreased by 97% @ 200 °C
70~80% @ 400 °C
- Magnitude of the damage strongly depends on the irradiation temperature.
 - It is better to keep the temperature of target around 400 ~ 800 °C






Target Remote Replacement Commissioning (Nov 2008)




1

Installation
of
manipulators
into hot cell




2

Offering up
target
replacement
system to
magnetic
horn



3

Disconnecting
target from
horn




4


Withdrawing
target from
horn




1st / 3rd Horn Operation Test



June 30, 2006



- 3rd horn test with support module: this fall
- 2nd horn fabrication is in progress at U.S.



April, 2007



beam

Graphite Target

$I=320\text{kA}$


1st Horn 2nd Horn 3rd Horn

1400 2000 2500

900 472 809 1400



1st horn prototype





Assembled into the K2K outer-conductor.







Horn1 Installation

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 36

- Installation succeeded on Jan. 21st.
- Target/OTR attached also.






Horn2

Shown in IFOP0812
LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 37

- US contribution
- Delivered to KEK at Mid. Jun.
- Test operation @ KEK (Tsukuba).
 - Mid. Aug ~ Early Oct.
 - ~ 230k pulses.
 - Distortion due to pulse is consistent with the expectation by FEM.
 - Measured magnetic field agrees with the design value in 1% level.







Structural interference is found during installation

- Interferences between horn modules and He vessel found during Nov & Dec. 2008
 - Modification become necessary
 - ~ 2 months delay was foreseen
- In order not to delay April beam commissioning, **we decided to**
 - **Operate Target & 1st horn only in the April beam commissioning**
 - postpone installation of 2nd and 3rd horn after commissioning (June~Sept, 2009)
- Commissioning with full setup after summer shutdown
 - With high power beam environment



No impact on T2K overall schedule





Dump




LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 39





Beam Dump


LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 40



- Design for the 2nd phase operation




- Plumbing finished on Feb. 15th
- Installation of side/upper iron shields finished Feb. 12th
- Concrete ceiling is under construction and will be finished by Mar. 16th





Hadron Absorber Module

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 42



- A design with multiple spring washers was adopted, to control joint force between graphite blocks and an aluminum cast cooling plate
- Flatness of the cooling surface and the loading surface < 0.1 mm
 - Machine 7 graphite blocks at once



Beam Dump

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 43



- Graphite core of BD was installed into the He vessel on Oct. 18th.




Muon monitor


LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 44

Installed the support structure
into the muon pit. (2/13)


Installed all 7 ionization chambers and
All of silicon PIN photodiodes.



Achieved alignment precision of 1 mm.



- Readout electronics is installed in Hut.
- Cabling / gas-piping is also finished.
- Measured noise-level during MR operation is small enough. ($\pm 0.5\text{mV}$)






Near Neutrino Detectors @ 280m

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 45



On-axis neutrino monitor

- Monitor
 - Profile
 - Direction
 - Intensity (& Energy)
- Iron-Scintillator sandwich detector
 - 1m x 1m x 10cm Iron
 - 1.25cm thick extruded Scinti.
 - New Photo-Sensor (MPPC/SiPM)



Detector
Hole

37m



Off-axis detector

- Measurement of ν flux and σ in the SK direction.
- Detector components.
 - UA1 magnet (0.2T)
 - TPC
 - Fine-Grained Scintillator detector (FGD)
 - Lead/Scintillator tracking detector for π^0
 - Electromagnetic Calorimeter
 - Muon Range Detector in mag
- Key technologies
 - Photo-sensor, Micromegas



JPARC visit - T2K target hall

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 46

Next up - my pictures

(apologize, ran out of time, notes in random order)



WOW - look at those doors !

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 47




Buildings are 20 cm concrete equiv.
for shielding radio-activated H₂O





T2K target hall top concrete shielding and horn staging/testing area


LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 48





Half of T2K target pile (other half covered)


LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 49





T2K target pile


LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 50





T2K target/horns water penetrations

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 51





T2K target pile mechanical room (1/3)

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 52




Support room space
extremely tight

Replacing anything big
will be extremely hard



Walkway


LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 53





Workcell in T2K target hall

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 54





Helium Vessel

T2K Helium Vessel leak rate:

They re-welded two areas on target-pile to decay-volume transition, after which leak rate met specification, stated to be 10^{-7} Pascal m^3/second ($\sim 10^{-6}$ $\text{cm}^3/\text{second}$ by my conversion but I don't see how one could measure to this level)

Evacuated to 50 Pascal (using 1 Atm = 10^5 pascal, reached 0.4 Torr, which is right around what the NuMI decay pipe ran at)

Compare helium vessel volume:

T2K: $\sim 1500 \text{ m}^3$

NuMI: $\sim 2000 \text{ m}^3$

DUSEL: ~ 3000 to 4000 m^3 ?

At least for now, they will exhaust helium and fill with new helium when replacing target or horn.

No scrubbing system for now.

Sealed volume, not follow atm. pressure variations.

Note target pile evacuated before helium fill.



T2K beam-line comparison

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 56

T2K	NuMI	Comment for ANU
Titanium beam window with remotely operable seal	Beryllium beam window without remote seal	Our smaller spot size favors Beryllium. Unless we are forced to replace the window, upgrading to a remote seal probably not sensible at this time.
Water cooled baffle (larger than NuMI, part of upstream shield wall)	Air cooled baffle	Air cooling gives one less water system to fail, provides larger temperature swing for beam-scraping monitoring
He cooled graphite target	H2O cooled graphite target	H2O makes more sense for us, but could look at graphite type. Since NOVA target does not have to fit in horn, water cooling is easier, and we have infrastructure already for water cooling, not helium.



T2K beam-line comparison

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 57

T2K	NuMI	Comment for ANU
Tried stir-friction welding horns, but resorted to TIG for final inner conductor welds	Horns TIG welded. Already copying stir-friction welding for producing strip-lines	
No coating on horns	OC anodized, IC nickel-plated	T2K in helium, NuMI in corrosive air.
Strip-line radial out from horn	Strip-line axial, then radial to allow for flexibility for thermal/alignment	At 700 kw, sufficient cooling of the axial stub is problematic for NuMI, under study
Ducts to carry cooling helium by strip-lines	Rely on general chase air-flow	At 700 kw, sufficient cooling of the axial stub is problematic for NuMI, under study



T2K beam-line comparison

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 58

T2K	NuMI	Comment for ANU
Horn remote water connection copied from NuMI	Compression fitting with nut turned by outer pipe welded to it	
Strip-line remote connection clamp copied from NuMI	Pressing plates to push strip-line prongs together	
Instrumentation remote connectors copied from NuMI	Ceramic-shell connectors guided in by daggers	
Horns hang from module, module is filled with shield blocks after installation, alignment is by moving whole module	Horns hang from module, module is filled with shield blocks after installation, horn 1 moves relative to module by motor-drive, horn 2 by moving whole module	NuMI can move horn 1 by re-aligning whole module at top, but involves shimming, is not easy.



T2K beam-line comparison

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 59

T2K	NuMI	Comment for ANU
Target chase, horns, decay volume, and absorber all in helium volume that can be evacuated	Decay volume is helium, target chase + horns + absorber are in air	Can't retrofit for NuMI, can consider for DUSEL. <i>Helium advantages: reduced corrosion, don't need large volume for air to decay before release to atmosphere. Dis-advantages: making pressure-tight volume, extra time for target-pile intervention.</i>
Target pile + decay volume walls water-cooled	Target pile air-cooled, decay volume water-cooled	Air-cooled target pile sufficient for ANU 700 kw
No decay-volume window (helium in both target pile and decay volume)	decay-volume upstream aluminum window not designed to be replaced	Could NuMI run with air in decay volume if window fails?



T2K beam-line comparison

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 60

T2K	NuMI	Comment for ANU
Surface building, several meters of top concrete shielding	Tunneled, uses the rock for final top-shielding, only 18" of top concrete shielding	DUSEL target hall could be either tunneled or pit-mined. Pit-mined could be filled-over or open-to-surface. Consider crane hook-height, shielding, air migration in choices.
Crane has duplicate motors in case of failure with hot item on crane	Crane has standard set of motors	Could/should NuMI crane be upgraded ?
Primary beam instrumentation includes ion profile monitor	Has SEM profile monitor and OTR profile monitor only	Thinking about ion profile monitor as eventual upgrade ?
How is alignment done ?		



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 61

320 kA, Horn 1 somewhere between 1 ms and 4 ms pulse,
some trouble with High Voltage

Extruded graphite at dump because cheaper
Carbon steel cooling pipe in cast aluminum pressing plates,
Trouble keeping flat as casting cooled
Surface tolerance 0.1 mm for good thermal contact

Deal with tritium exiting blue blocks?

-> they don't use blue blocks,

The JPARC hadron hall uses hundreds of blue blocks

Blue Block supplier Duratek changed to Energy Solutions,
ran out of U.S. radiated steel, now importing.

Capacity ~ 50 blocks / year, JPARC has them on order

NuMI order of magnitude without looking anything up ~ 400 blocks

~ 4,000 tons x \$600 / ton = \$2.4 million worth of steel
but we got it for ~ \$0.1 million



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 62

Time for horn change-out? Months (up to six ?)

Repair strategy for helium vessel? ...

Seal penetration around strip-lines through He vessel wall?

G10 and epoxy

Did concrete poured around strip-line work out?

did not use this

Remote water connection?

copied from NuMI

Strip-line connection?

pretty much copied from NuMI, but not removable strip-line block,
replace entire module if remote clamp fails.

Allowance for stripline thermal expansion?

use helium duct to keep stripline cool



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 63

Alignment tolerances?

Horn 1 -> 1 mm, Horn 2 and 3 -> 3 mm

Instrumentation for targeting, horns?

OTR at target

NUMI has final straight section without magnets ~12 m,

T2K has magnets right up to the pile wall.

(T2K spec. 1 mr, NuMI almost order of magnitude tighter)

"What have you learned that might not be obvious to us?

What worked well, what would you rather have done differently?"

"ask us after we have run"



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylan/FNAL
Page 64

T2K has no hadron monitor.

Horn construction:

- Ceramic ring like NuMI but larger
- no coatings

- horn water drain system similar to NuMI,
- self-priming pump on edge of operable height
- (pump on top like NuMI) almost 9 m of lift for water

Monitoring for horn deterioration?

Crane capacity? 43 ton main and 15 ton aux
1 level of redundancy for all motors on main crane
(not on small crane)

Asked about removing crane electronics -
they think level will be low enough not to have to.
Horn module about 15 ton, but need main crane
because of redundancy.



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylan/FNAL
Page 65

Fraction of running for neutrinos?

(130 days per year from a talk on web)

(Since May 1, 2005 NuMI has had beam for average of 262 days/year)

Very clean - they put down plastic and plywood over the epoxy coated floor so delivery trucks would not mar the surface.

1/2 meter concrete end-of-transfer-line to target-pile
(seems short ?)

Baffle dimensions ~ 1 inch hole, 1.7 m long

110 m from target to dump

20 people limit in ND hall

wow what nice elevators !

3.5 deg slope of beam

Want 1 mr accuracy → 30 cm at ND 280 m on-axis monitor



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylan/FNAL
Page 66

Muon monitor 10^8 particle/cm²
less than our hadron monitor ($\sim 2 \times 10^9$),
but higher than our muon monitor

Some areas of JPARC have sunk ~ 1 inch
Piles were to be sunk 25 to 50 m to bedrock
below sand, but studies said 30 m in sand was OK.

15×10^{13} /pulse
increase rep rate to compensate for 30 GeV vs 50 GeV
30 GeV 0.5 Hz 750 kw for foreseeable future
ring is 9 bunches or 18 bunches, initial running
9 (minus one for gap) bunches 5 microsecond spill

Poured concrete over decay pipe and beam dump,
limits repair capability
Beam dump is in helium volume.

Muon monitor after helium volume.



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 67

proton beam 0.6 cm sigma beam spot

DK collimator limits power to decay walls

For Access, where do shielding-blocks go?
did not get answer, may have to move outside.

Power spray: 1/3 target hall, 1/3 DK, 1/3 dump

Aluminum cover of target hall helium vessel
(two pieces, with port for OTR)

1.2cm thick decay iron

10 cm water-cooled steel helium vessel around horn
then steel shielding air cooled then concrete

Earthquake brace inside helium vessel interfered with
stripline on horn, they will modify stripline by fall.



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 68

Some areas of JPARC have sunk ~ 1 inch
Piles were to be sunk 25 to 50 m to bedrock
below sand, but studies said 30 m in sand was OK.

15×10^{13} /pulse

increase rep rate to compensate for 30 GeV vs 50 GeV

30 GeV 0.5 Hz 750 kw for foreseeable future

ring is 9 bunches or 18 bunches, initial run

is 9 (minus one for gap) bunches 5 microsecond spill

Poured concrete over decay pipe and beam dump

Beam dump is in helium volume.

proton beam 0.6 cm sigma beam spot, titanium window

DK collimator limits power to decay walls



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 69

For Access, where do shielding-blocks go?
did not get answer, may have to move outside.

Power spray: 1/3 target hall, 1/3 DK, 1/3 dump

Aluminum cover of target hall helium vessel
(two pieces, with port for OTR)
1.2cm thick decay iron
10 cm water-cooled steel helium vessel around horn
then steel shielding air cooled then concrete

Earthquake brace inside helium vessel interfered with
stripline on horn, they will modify stripline by fall.

We have a replaceable stripline block for remote
horn connection; they have remote connector permanently
mounted on module.



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
March 23, 2009
Jim Hylen/FNAL
Page 70

We have a replaceable stripline block for remote horn connection; they have remote connector permanently mounted on module.

Helium compressors are in mechanical room -
helium lines to cool horns must penetrate vessel walls?

1.6 km around ring for 9 bunch but 1 for kicker = 8 bunch
each bunch around 10 m long -> 30 ns

Patrick says shielding "T-Blocks" were zinc-clad steel

note target helium is separate system from vessel helium
because vessel helium may not be pure enough to prevent
oxidation of the target graphite