



JPARC visit - T2K target hall

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hlyen/FNAL
Page 1

Tour of 50 GeV accelerator, hadron hall, T2K target hall/absorber/near detector

Had only short time with target hall experts, who are extremely busy getting ready to turn beam on to T2K target next month, but graciously took time out to show us the facility.

The timing of the trip was set by trying to get there before things became irradiated; knowing what things work well will come with a few years operating experience.



Note T2K permanent facilities (dump, shielding) designed for up to 4 MW, but replaceable items (collimator, window, target, horns) designed for 0.75 MW.

Will show

- Overview slides of beam-line "borrowed" from publicly available T2K talks
Takashi Kobayashi, Chris Densham, Atsuko Ichikawa
- A few pictures we took
- Some comparisons to NuMI
- Some comments about what is transferable to DUSEL beam

(Accuracy warning: there is a reason hear-say is not admissible in court)



Some issues for LBNE (DUSEL beam)

? surface pit versus mining for target hall

Containment of gas radio-isotopes

Very large hook-height

Shield blocks versus overhead dirt/rock

Cheaper to have very large support rooms on surface ?

? inert gas in sealed target pile

Advantages:

Reduces corrosion (e.g. NuMI nickel flakes)

Reduces and contains short-lived radio-isotopes in gas

Some reduction in tritium (significant or not?)

Dis-advantages:

No way to fix helium leak if there is a failure (?)

Significantly raises the bar for interventions in target pile

Need walls to withstand vacuum (?)

Helium is not as good at standing off high voltage for horns



Some issues for LBNE (DUSEL beam)

- ? failure of crane during hot pick
 - Pull component directly into coffin ?
 - Side load so don't use crane, but rollers ?
 - Put lots of redundancy on crane ?

- ? how to handle tritium

- ? inert gas around dump

- ? Monitoring beam



JPARC visit - T2K target hall

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hlyen/FNAL
Page 4

JPARC

short facility, 110 m target to dump

DUSEL

200 to 300 m DK



This and next bunch is borrowed slides

LBNE (DUSEL beam) Mtg.
 April 6, 2009
 Jim Hlyen/FNAL
 Page 5

A T2K Roadmap – as of end of last year

	Day1 (up to Jul.2010)	Next Step	KEK Roadmap	Ultimate? [Not official any more]
Power(MW)	0.1	0.45	1.66	[3-4 MW] ? [Original objective]
Energy(GeV)	30	30	30	[50]
Rep Cycle(sec)	3.5	3-2	1.92	
No. of Bunch	6	8	8	[8]
Particle/Bunch	1.2×10^{13}	$< 4.1 \times 10^{13}$	8.3×10^{13}	
Particle/Ring	7.2×10^{13}	$< 3.3 \times 10^{14}$	6.7×10^{14}	
LINAC(MeV)	181	181	400	
RCS	h=2	h=2 or 1	h=1	

After 2010, plan depends on financial situation



Target station

- Target & horns in helium vessel
- Helium vessel and iron shields cooled by water


Decay Volume


- 94m long helium vessel cooled by water
- 6m thick concrete shield


Hadron Absorber

(Beam Dump)

- graphite core in helium vessel








- Baffle
- 3 horns Hanged by support module.
- Target ... installed in the 1st horn.
- OTR (Optical Transition Radiation monitor): attached to 1st horn





Target Station

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 9



Beam window
(designed in RAL)










Horn & support module


NE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 11



Horn Support Module





Cast Iron Shield Block
[1/10 model]



Baffle



Helium Vessel Construction




Installation for the bottom plates has been completed



Upper box on the Super-Carrier (Nakaminato port)

• Installation is going on !



Feb. 3, 2009





Feb. 10, 2009

- **Vacuum test of He vessel finished on Feb. 18th.**
 - All TS+DV+BD connected to one BIG vessel ($\sim 3\text{m} \times \sim 5\text{m} \times \sim 100\text{m} = \sim 1500\text{m}^3$)
 - Evacuated down to 50 Pa by three pumps
 - **No leak found** after two repairs at the connection between DV-BD
- Ceiling concrete blocks will be installed from Mar. 9th to 16th.



Decay Volume

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 14





Beam Window

Top plate


Ti-6Al-4V Double
Beam window

Helium inlet

Pantograph mechanism


Pillow seal (mates
with mirror finished
flange on either side)

Support casing






Helium cooling of beam window



The finished window skins
(by RAL workshop):



Helium velocity ≈ 5 m/s





Monitor stack and Window

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylan/FNAL
Page 17



Monitor stack (TRIUMF)
installed on Oct. 22nd.




The beam window from RAL
was installed on Oct. 23rd.





Collimator

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylan/FNAL
Page 18





- Beam collimator in front of the 1st horn
- Designed & Build in UK
- Installation succeeded on Jan. 10th.







OTR (Canada)

LBNE (DUSEL beam) Mtg.
April 6, 2009
FNAL
page 20



Calibration image



Backlit Foil w Holes



Undistorted



- Profile monitor just in front of target
- Foil structure is installed to 1st horn module.
- Optical path (Mirrors) is aligned and calibration image is obtained.
- Cabling, Installation of optical table on going




Target - (UK)


- Graphite rod, 900 mm (2 interaction lengths) long, 26 mm ($c.2\sigma$) diameter
- **c.20 kW (3%)** of **750 kW** Beam Power dissipated in target as heat
- Helium cooled (i) to avoid shock waves from liquid coolants e.g. water and (ii) to allow higher operating temperature
- Target rod completely encased in titanium to prevent oxidation of the graphite
- Helium cools both upstream and downstream titanium window first before cooling the target due to Ti-6Al-4V material temperature limits
- Pressure drop in the system should be kept to a minimum due to high flow rate required (max. 0.8 bar available for target at required flow rate of 32 g/s (30% safety margin))
- Target to be uniformly cooled (but kept above 400°C to reduce radiation damage)
- It should be possible to remotely change the target in the first horn



Target Design: Helium cooling path



Flow turns 180° at downstream window





Diffusion Bond +


Graphite-Graphite bonding test

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 23

IG43 Graphite diffusion bonded into Ti-6Al-4V titanium, Special Techniques Group at UKAEA Culham



Graphite transfer to Aluminium



Graphite-Graphite bonding



Aluminium intermediate layer, bonding temperature 550°C
Soft aluminium layer reduces residual thermal stresses in the graphite




30 GeV, 0.4735Hz, 750 kW beam

Radiation damaged graphite assumed (thermal conductivity
20 [W/m.K] at 1000K- approx 4 times lower than new
graphite)

CFX



Maximum temperature = 736°C







Helium cooling velocity streamlines

Velocity (Streamline 1) Maximum velocity = 398 m/s




Pressures (gauge)

Pressure drop = 0.792 bar







Helium-Cooled Graphite Target in the 1st Horn



CFX


Helium gas cooling system is
in hand and being tested.


Velocity
(Streamline 1)
4.132e+02
3.099e+02
2.066e+02
1.033e+02
2.080e-02
[m s⁻¹]



$\Delta T \sim 200K \sim 7MPa$ (Tensile 27MPa)

Full prototype to be delivered in Dec.









Pulsed beam induced thermal stress waves in target graphite


Max. Von Mises Stress = 7 MPa
- cf graphite strength ~37 MPa
- should be OK

VonMises_centre
Long_stress_centre
Hoop_stress_centre
VonMises_radius
Hoop_stress_radius





Radiation Damage in IG43 Graphite - data from Nick Simos, BNL



200 MeV proton fluence

$\sim 10^{21}$ p/cm²

c. 1 year operation in T2K

(phase 1, 750 kW)

We don't expect targets to last long!

Targets can be changed within magnetic horn



Irradiation effects on Graphite



LBNE (DUSEL beam) Mtg.

April 6, 2009

Jim Hylen/FNAL

Page 30

- Expected radiation damage of the target
 - The approximation formula used by NuMI target group : 0.25dpa/year
 - MARS simulation : 0.15~0.20 dpa/year
- Dimension change : shrinkage by ~5mm in length in 5 years at maximum.
~75 μ m in radius
- Degradation of thermal conductivity ... decreased by **97%** @ 200 °C
70~80% @ 400 °C
- Magnitude of the damage strongly depends on the irradiation temperature.
 - It is better to keep the temperature of target around **400 ~ 800 °C**






Target Remote Replacement Commissioning (Nov 2008)




1

Installation
of
manipulators
into hot cell




2

Offering up
target
replacement
system to
magnetic
horn



3

Disconnecting
target from
horn



4


Withdrawing
target from
horn




1st / 3rd Horn Operation Test



June 30, 2006




- 3rd horn test with support module: this fall
- 2nd horn fabrication is in progress at U.S.





After consideration on the stress analysis, we decided to make inner-conductors w/ 3mm-thick aluminum.





1st horn prototype





Assembled into the K2K outer-conductor.






Horn1 Installation

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 36

- Installation succeeded on Jan. 21st.
- Target/OTR attached also.






Horn2

Shown in IFOP0812
LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylan/FNAL
Page 37


- US contribution
- Delivered to KEK at Mid. Jun.
- Test operation @ KEK (Tsukuba).
 - Mid. Aug ~ Early Oct.
 - ~ 230k pulses.
 - Distortion due to pulse is consistent with the expectation by FEM.
 - Measured magnetic field agrees with the design value in 1% level.







Structural interference is found during installation

- Interferences between horn modules and He vessel found during Nov & Dec. 2008
 - Modification become necessary
 - ~ 2 months delay was foreseen
 - In order not to delay April beam commissioning, **we decided to**
 - **Operate Target & 1st horn only in the April beam commissioning**
 - postpone installation of 2nd and 3rd horn after commissioning (June~Sept, 2009)
 - Commissioning with full setup after summer shutdown
 - With high power beam environment
- No impact on T2K overall schedule**








Dump





Beam Dump



- Design for the 2nd phase operation




- Plumbing finished on Feb. 15th
- Installation of side/upper iron shields finished Feb. 12th
- Concrete ceiling is under construction and will be finished by Mar. 16th



Hadron Absorber Module

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 42



- A design with multiple spring washers was adopted, to control joint force between graphite blocks and an aluminum cast cooling plate
- Flatness of the cooling surface and the loading surface $< 0.1 \text{ mm}$
 - Machine 7 graphite blocks at once



Beam Dump

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 43



- Graphite core of BD was installed into the He vessel on Oct. 18th.




Muon monitor


LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 44

Installed the support structure
into the muon pit. (2/13)

Installed all 7 ionization chambers and
All of silicon PIN photodiodes.



- Readout electronics is installed in Hut.
- Cabling / gas-piping is also finished.
- Measured noise-level during MR operation is small enough. ($\pm 0.5\text{mV}$)



Achieved alignment precision of 1 mm.






Near Neutrino Detectors @ 280m

LBNE (DUSEL beam) Mtg.
 April 6, 2009
 Jim Hlyen/FNAL
 Page 45

On-axis neutrino monitor

- Monitor
 - Profile
 - Direction
 - Intensity (& Energy)
- Iron-Scintillator sandwich detector
 - 1m x 1m x 10cm Iron
 - 1.25cm thick extruded Scinti.
 - New Photo-Sensor (MPPC/SiPM)



□ Conceptual design optimization versus PIT

Off-axis detector

- Measurement of ν flux and σ in the SK direction.
- Detector components.
 - UA1 magnet (0.2T)
 - TPC
 - Fine-Grained Scintillator detector (FGD)
 - Lead/Scintillator tracking detector for π^0
 - Electromagnetic Calorimeter
 - Muon Range Detector in mag
- Key technologies
 - Photo-sensor, Micromegas



JPARC visit - T2K target hall

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hlyen/FNAL
Page 46

Next up - my pictures and notes

Highlight:

- Remote connections
- Differences due to helium filled target pile
- Differences due to surface target hall



Underground - real elevators rather than cages !

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 47





WOW - look at those doors !



Buildings are 20 cm concrete equiv.
for shielding radio-activated H₂O


(downside of surface bldg?)





target pile top concrete shielding is massive
(surface bldg. equivalent of our rock/dirt cover,
slows down repairs)


LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 49





Half of T2K target pile (other half covered)


LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 50





Half of T2K target pile

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylan/FNAL
Page 51





Pre-target to target hall transition

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 52

Pre-target beam magnets right up to target hall wall
(compare NuMI 10 m of straight section to define proton beam angle)

Wall is $\sim \frac{1}{2}$ m of concrete, before target pile steel. (NuMI 6' concrete)



T2K spec on beam
angle is ~ 1 mr

NuMI an order of
magnitude tighter



Crane



Crane operator's control station has window to T-hall (to supplement cameras)


Main 40 T crane has duplicate motors in case of failure with hot item (not on smaller 15 T crane)





Lifting fixture

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 54



Commercial system where
bottom part of pin rotates to
lock into shielding block
(believe this is normally used for
shipping containers)

(NuMI used just a home-grown
open hook system)



T2K target hall - horn/module test area

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 55





Horn drain tank, pump-out lines

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 56



Like NUMI but
dual pump-out lines

Pump on top like NuMI

On edge of
operable height.
(Almost 9 m of lift
for water)

Pump-out was
problematic for NuMI,
so redundancy
sounds good



Horns - drain and electrical isolation

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylan/FNAL
Page 57




The NuMI horn electrical isolation is at the hanger above the horn, which we repaired several times.

Not sure this could be repaired, but CNGS did repair this seal on their horn 2 after a short period of running.



Horn support cooling

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylan/FNAL
Page 58




The horn support beams are water-cooled (U shaped loop)

(The water-cooled NuMI hanger for horn 1 was a source of a water leak, NuMI horn 2 did not need the cooling)



Horn hanging from module similar to NuMI

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 59




Remote water & instrumentation-line connections copied from NuMI.
Note strip-line sections clamped together (NuMI welded)



Horn water spray

Water spray ports with electrical isolation and drains as per Mini-BOONE





Strip-line and remote clamp

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylan/FNAL
Page 61




Jog to remove
line-of-sight
Duct flows helium
to cool stripline



Strip-line remote
clamp a la NUMI,
but permanently
fixed to module


(NuMI strip-line block is replaceable;
T2K helium may make this less risky)





Horn alignment via translation of entire module

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylan/FNAL
Page 62



NuMI has shafts through module for target, horn 1, but I would not repeat that, this makes more sense.



Transformers between power supply and horns

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 63



Horn 1 has separate transformer, Horns 2 and 3 are run in series.
Transformers are from K2K beam-line, mildly radioactive.
(NuMI: No transformers, Horns 1 & 2 in series)



Strip-line penetration to helium volume

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylan/FNAL
Page 64


G10 electrical isolation
with epoxy gas seal





T2K target/horns water & helium penetrations

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hysten/FNAL
Page 65





T2K target pile mechanical room (1/3)

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 66




Support room space
extremely tight

Replacing anything big
will be extremely hard



Walkway


LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylan/FNAL
Page 67





Work-cell in T2K target hall

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 68





Helium Vessel

T2K Helium Vessel leak rate:

They re-welded two areas on target-pile to decay-volume transition, after which leak rate met specification, stated to be 10^{-7} Pascal m^3 /second ($\sim 10^{-6}$ cm^3 /second by my conversion but I don't see how one could measure to this level)

Evacuated to 50 Pascal (using 1 Atm = 10^5 pascal, reached 0.4 Torr, which is right around what the NuMI decay pipe ran at)

Compare helium vessel volume:

T2K: ~ 1500 m^3

NuMI: ~ 2000 m^3

DUSEL: ~ 3000 to 4000 m^3 ?

At least for now, they will exhaust helium and fill with new helium when replacing target or horn.

No scrubbing system for now.

Sealed volume, not follow atm. pressure variations.

Note target pile evacuated before helium fill.



T2K beam-line comparison

T2K	NuMI	Comment
Titanium beam window with remotely operable seal	Beryllium beam window without remote seal	Our smaller spot size favors Beryllium. LBNE may want to copy remote seal.
Water cooled baffle (larger than NuMI, part of upstream shield wall)	Air cooled baffle	Air cooling gives one less water system to fail, provides larger temperature swing for beam-scraping monitoring
He cooled graphite target	H ₂ O cooled graphite target	Target requires a lot of study



T2K beam-line comparison

T2K	NuMI	Comment
Tried stir-friction welding horns, but resorted to TIG for final inner conductor welds	Horns TIG welded. Already copying stir-friction welding for producing strip-lines	
No coating on horns	OC anodized, IC nickel-plated	T2K in helium, NuMI in corrosive air. LBNE in ??
Strip-line radial out from horn	Strip-line axial, then radial to allow for flexibility for thermal/alignment	At 700 kw, sufficient cooling of the axial stub is problematic for NuMI, under study
Ducts to carry cooling helium by strip-lines	Rely on general chase air-flow	Must improve NuMI design for LBNE



T2K beam-line comparison

T2K	NuMI	Comment
Horn remote water connection copied from NuMI	Compression fitting with nut turned by outer pipe welded to it	
Strip-line remote connection clamp copied from NuMI	Pressing plates to push strip-line prongs together	
Instrumentation remote connectors copied from NuMI	Ceramic-shell connectors guided in by daggers	
Horns hang from module, module is filled with shield blocks after installation, alignment is by moving whole module	Horns hang from module, module is filled with shield blocks after installation, horn 1 moves relative to module by motor-drive, horn 2 by moving whole module	NuMI can move horn 1 by re-aligning whole module at top, but involves shimming, is not easy. LBNE copy T2K?



T2K beam-line comparison

T2K	NuMI	Comment
Target chase, horns, decay volume, and absorber all in helium volume that can be evacuated	Decay volume is helium, target chase + horns + absorber are in air	<i>Helium advantages: reduced corrosion, don't need large volume for air to decay before release to atmosphere. Disadvantages: making pressure-tight volume, extra time for target-pile intervention.</i>
Target pile + decay volume walls water-cooled	Target pile air-cooled, decay volume water-cooled	Air-cooled target pile sufficient for ANU 700 kw, but believe will need water-cooled inner shielding for LBNE
No decay-volume window (helium in both target pile and decay volume)	decay-volume upstream aluminum window not designed to be replaced	Could NuMI run with air in decay volume if window fails? Decay pipe upstream window should be replaceable or eliminated for LBNE



T2K beam-line comparison

T2K	NuMI	Comment
Surface building, several meters of top concrete shielding	Tunneled, uses the rock for final top-shielding, only 18" of top concrete shielding	LBNE target hall could be either tunneled or pit-mined. Pit-mined could be filled-over or open-to-surface. Consider crane hook-height, shielding, air migration in choices.
Crane has duplicate motors in case of failure with hot item on crane	Crane has standard set of motors	Could/should NuMI crane be upgraded ?
Primary beam instrumentation includes ion profile monitor	Has SEM profile monitor and OTR profile monitor only	Thinking about ion profile monitor as eventual upgrade ?
How is alignment done ?		



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylan/FNAL
Page 75

Extruded graphite at dump because cheaper
Carbon steel cooling pipe in cast aluminum pressing plates,
Trouble keeping flat as casting cooled
Surface tolerance 0.1 mm for good thermal contact

Deal with tritium exiting blue blocks?

-> they don't use blue blocks,

The JPARC hadron hall uses hundreds of blue blocks

Blue Block supplier Duratek changed to Energy Solutions,
ran out of U.S. radiated steel, now importing.

Capacity ~ 50 blocks / year, JPARC has them on order

NuMI order of magnitude without looking anything up ~ 400 blocks

~ 4,000 tons x \$600 / ton = \$2.4 million worth of steel
but we got it for ~ \$0.1 million



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hlyen/FNAL
Page 76

Time for horn change-out? Months (up to six ?)

We did not have time to discuss their change-out procedure,
but the extensive top-shielding and the helium vessel certainly have impact

Repair strategy for helium vessel? ...



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 77

320 kA, Horn 1 somewhere between 1 ms and 4 ms pulse,
some trouble with High Voltage

Alignment tolerances?

Horn 1 -> 1 mm, Horn 2 and 3 -> 3 mm (similar to NuMI/NOVA)

Instrumentation for targeting, horns?

OTR at target (note a single monitor can give X, Y
but not vertical and horizontal angles;
NuMI/Nova handles angles by scanning
baffle+target system, doesn't work for T2K/LBNE)



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylan/FNAL
Page 78

Horn construction:

Ceramic ring like NuMI but larger (special Japanese vendor)
no coatings

Monitoring for horn deterioration?

Asked about removing crane electronics -
they think level will be low enough not to have to.

Horn module about 15 ton, but use main crane on it
because of crane redundancy.



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 79

Fraction of running for neutrinos?

(130 days per year from a talk on web)

(Since May 1, 2005 NuMI has had beam for average of 262 days/year)

15×10^{13} /pulse proton beam 0.6 cm sigma beam spot

increase rep rate to compensate for 30 GeV vs 50 GeV

30 GeV 0.5 Hz 750 kw for foreseeable future

1.6 km around ring for 9 bunch but 1 for kicker = 8 bunch

each bunch around 10 m long -> 30 ns, 5 microsecond spill

May increase to 18 (16?) bunches



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 80

T2K has no hadron monitor.

Muon monitor 10^8 particle/cm²
less than our hadron monitor ($\sim 2 \times 10^9$),
but higher than our muon monitor

Some areas of JPARC have sunk ~ 1 inch
Piles were to be sunk 25 to 50 m to bedrock
below sand, but studies said 30 m in sand was OK.

Very clean - they put down plastic and plywood over
the epoxy coated floor so delivery trucks would not mar the surface.

Poured concrete over decay pipe and beam dump rather than shield blocks,
limits repair capability (done for budget reasons)

Beam dump is in helium volume.

Muon monitor is after helium volume.



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylen/FNAL
Page 81

DK collimator at end of target hall limits power to decay walls

For Access, where do shielding-blocks go?
did not get answer, may have to move outside.

Power spray: 1/3 target hall, 1/3 DK, 1/3 dump

Aluminum cover of target hall helium vessel
(two pieces, with port for OTR)

1.2cm thick decay iron

10 cm water-cooled steel helium vessel around horn
then steel shielding air cooled then concrete

Earthquake brace inside helium vessel interfered with
Strip-line on horn, delaying installation of horns 2 and 3,
they will modify strip-line by fall.



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hylan/FNAL
Page 82

Patrick says shielding "T-Blocks" were zinc-clad steel

note target helium is separate system from vessel helium
because vessel helium may not be pure enough to prevent
oxidation of the target graphite



JPARC visit - T2K target hall notes

LBNE (DUSEL beam) Mtg.
April 6, 2009
Jim Hlyen/FNAL
Page 83

20 people limit in ND hall

Near Detector on-axis is deep because of 3.5 deg slope of beam
Want 1 m accuracy -> 30 cm at ND 280 m on-axis monitor

"What have you learned that might not be obvious to us?
What worked well, what would you rather have done differently?"
"ask us after we have run"